

15-179-00210-00-07

UNION OIL COMPANY OF CALIFORNIA
Wichita, Kansas

Brutt No. 1
ONW NE SW Section 23-33-26W
Sheridan County, Kansas

Casing Record:
13-3/8" surface casing cemented
at 253' with 200 sax.
5-1/2" casing cemented at 3899'
with 150 sax.
Elevation: 2310' D 7
2507 GA

Commenced: January 16, 1943
Completed: March 8th, 1943

<u>LOG</u>			<u>TOPS</u>	
<u>From</u>	<u>To</u>	<u>Formation</u>	Sample tops adjusted to Schlumberger:	
0	255	Surface	Dakota	1090
255	315	Lime & shale	Anhydrite	2150
315	1259	Shale & sand	Topeka	3425
1259	1570	Shale & shells	Lansing-Kansas City	3687
1570	2142	Shale & Red bed	Base Kansas City	3904
2142	2160	Anhydrite	Pennsylvania Basal Cong.	4170
2160	2180	Not logged	Mississippi	4195
2180	2215	Lime	Base Mississippi	4309
2215	2226	Shale	Arbuckle	4313
2226	2250	Shale & lime		
2250	2435	Red bed, shale & shell	T.D.	4444
2435	2530	Shale & shells		
2530	2700	Shale & lime		
2700	2935	Lime & shale	(Measurements from drive bushing)	
2935	3060	Shale & lime	(2' above derriek floor.)	
3060	3094	Black shale		
3094	3133	Shale		
3133	3240	Shale & lime		
3240	3322	Lime & shale		
3322	3423	Lime (soft)		
3423	3566	Lime & shale		
3566	3646	Lime		
3646	3741	Lime & shale		
3741	3900	Lime		
3900	3939	Lime & shale		
3939	3995	Shale & lime		
3995	4043	Lime & shale		
4043	4176	Shale & lime		
4176	4204	Shale		
4204	4215	Lime & chert		
4215	4227	Chert		
4227	4259	Chert & lime		
4259	4315	Lime		
4315	4332	Lime chert		
4332	4348	Lime		
4348	4358	Soft dolomite		
4358	4358	Lime		
4358	4435	Lime & chert		
4435	4444	Chert & dolomite		

RECEIVED
STATE CORPORATION COMMISSION

JAN 6 1966
1-6-1966
CONSERVATION DIVISION
Wichita, Kansas

Perf. 3808 to 3817 - one shot per foot
2800' O I H 40/50 minutes
Well started to flow in 1-1/2 hours
Shot 3810 to 3817 with 20 additional shots
Well flowed approx. 6 bbls. per hour for 12 hours
Shut in