

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

RECEIVED
CORPORATION COMMISSION
NOV 30 2007
CONSERVATION DIVISION
WICHITA, KS

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Castelli Exploration, Inc.

Address: 6908 NW 112th St, Oklahoma City, OK 73162

Phone: (405) 722-5511 Operator License #: 31021

Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: Nov. 13, 2007 (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Never Produced

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 033214540000

Lease Name: Hashknife

Well Number: 1-9

Spot Location (QQQQ): NW - SE - NE -
1520 Feet from North / South Section Line

875 Feet from East / West Section Line

Sec. 9 Twp. 31 S. R. 16 East West

County: Comanche

Date Well Completed: 11-26-05

Plugging Commenced: 11-13-07

Plugging Completed: 11-14-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0'	65'	24"	65'	0
			308'	13 3/8"	308'	
			4964'	4 1/2"	117 jts	3250'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 30 sacks cement down 4 1/2" to 4350', shut in, checked hole, cement was at 4350', dug cellar, unpacked casing head, set floor, pulled slips, cut surface off 4' below ground, had 23" stretch, ripped casing at 3420', worked pipe, ripped casing at 3250', worked pipe free, pulled casing up to 1000', pumped 15 gel, 50 sacks cement, pulled to 320', pumped 80 sacks, pulled to 40', pumped 40 sacks to surface.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 190 US Highway 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: Castelli Exploration, Inc.


State of Oklahoma County, Oklahoma, ss.

Thomas P. Castelli (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Thomas P. Castelli
(Address) 6908 N.W. 112th St. Oklahoma City, OK 73162

SUBSCRIBED and SWORN TO before me this 27th day of November, 2007

Tisha L. Braun My Commission Expires: 6/23/08
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]

Quality Well Service, Inc.

190 US Highway 56
Ellinwood, KS 67526

Invoice

Date	Invoice #
11/20/2007	922

Bill To
Castelli Exploration, Inc. 6908 NW 112th Oklahoma City, OK 73162

P.O. No.	Terms	Lease Name
	net	Hashknife 1-9

Description	Qty	Rate	Amount
Rig Time	23	175.00	4,025.00T
Floor Rental		125.00	125.00T
Shots	2	160.00	320.00T
Torch		50.00	50.00T
Water Truck	2.5	75.00	187.50T
Backhoe	2.5	75.00	187.50T
Out of Town		120.00	120.00T
Phone Calls		15.00	15.00T
Clerical		20.00	20.00T
Wiping Rubber		20.00	20.00T
11-13-07 Drove to location, raised pole, checked hole, pumped 30 sacks cement down 4 1/2" to 4350', shot in, drove to motel.			
11-14-07 Drove to location, checked hole, cement was at 4350', dug cellar, unpacked casing head, set floor, pulled slips, cut surface off 4' below ground, had 23" stretch, ripped casing at 3420', worked pipe, ripped casing at 3250', worked pipe free, pulled casing up to 1000', pumped 15 gel, 50 sacks cement, pulled to 320', pumped 80 sacks, pulled to 40', pumped 40 sacks to surface, tore down floor and rig.			
Subtotal			\$5,070.00
Sales Tax (5.3%)			\$268.71
Total			\$5,338.71

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 30 2007

CONSERVATION DIVISION
WICHITA, KS

Quality Oilwell Cementing Inc.

Invoice

740 W WICHITA
P.O. Box 32
Russell, KS 67665

Date	Invoice #
11/19/2007	588

Bill To
Castelli Exploration Inc 6908 NW 112th St Oklahoma City Ok 73162

P.O. No.	Terms	Project
	Net 30	

Quantity	Description	Rate	Amount
1	4 1/2" rubber plug	52.00	52.00T
1	pump truck charge PUMP BOTTOM	700.00	700.00T
39	pump truck mileage charge	6.00	234.00T
99	discount 10% if paid within 30 days DISCOUNT HAS ALREADY BEEN DEDUCTED	-1.00	-99.00
	LEASE: HASH KNIFE WELL #1-9 Comanche county Sales Tax	5.30%	52.26

CASTELLI EXPLORATION, INC.

URLG _____ COMP _____ L.O.E.

TANG TANG _____

LEASE # 29802 G.L. # 24183

USED FOR _____

WELL COR.# 64600

DL 11/27/07

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 30 2007
CONSERVATION DIVISION
WICHITA, KS

Thank you for your business. Dave

Total \$939.26

Quality Oilwell Cementing Inc.

Invoice

740 W WICHITA
 P.O. Box 32
 Russell, KS 67665

Date	Invoice #
11/19/2007	589

Bill To
Castelli Exploration Inc 6908 NW 112th St Oklahoma City Ok 73162

P.O. No.	Terms	Project
	Net 30	

Quantity	Description	Rate	Amount
132	common	11.00	1,452.00T
88	POZ	6.05	532.40T
24	GEL	17.00	408.00T
4	hulls	25.00	100.00T
248	handling	1.90	471.20T
9,672	.08 * 248 SACKS * 39 MILES	0.08	773.76T
1	4 1/2" rubber plug	52.00	52.00T
1	pump truck charge plugging	350.00	350.00T
414	discount 10% if paid within 30 days DISCOUNT HAS ALREADY BEEN DEDUCTED	-1.00	-414.00
	LEASE: HASH KNIFE WELL #1-9 Comanche county Sales Tax	5.30%	219.39

CASTELLI EXPLORATION, INC.

DRLG _____ COMP _____ L.O.E.
 INTANG TANG _____
 LEASE # 29802 G.L. # 74183
 USED FOR _____
 VENDOR# 64600

RECEIVED
 KANSAS CORPORATION COMMISSION
NOV 30 2007
 CONSERVATION DIVISION
 WICHITA, KS

Thank you for your business. Dave	Total	\$3,944.75
-----------------------------------	--------------	------------

QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 1428

Date	11-13-07	Sec.	9	Twp.	31	Range	16	Called Out		On Location		Job Start	3:30	Finish	4:30	
Lease	Hashkafe	Well No.	1-9			Location			29 miles W 10 miles N of Medicine Lodge			Comanche County	KS	State		
Contractor	Quality Well Service						Owner									
Type Job	Pumped Bottom						To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.									
Hole Size							T.D.									
Csg.							Depth									
Tbg. Size							Depth									
Drill Pipe							Depth									
Tool							Depth									
Cement Left in Csg.							Shoe Joint									
Press Max.							Minimum									
Meas Line							Displace									
Perf.							Cement ✓ Hulls Charge on Ticket 1429 Amount Ordered 30 SKS 60/40 4% Gel									
EQUIPMENT																
Pumptrk	6	No.	Cementer	David			Consisting of									
			Helper				Common									
Bulktrk	3	No.	Driver	Rich			Poz. Mix									
			Driver				Gel.									
Bulktrk		No.	Driver	Dean			Chloride									
			Driver				Hulls 4 # X → 25 ⁰⁰									
JOB SERVICES & REMARKS																
Pumptrk Charge	1st Day pump Bottom plug						200 ⁰⁰									
Mileage	39 @ 6 ⁰⁰						234 ⁰⁰									
Footage							Total 934 ⁰⁰									
Remarks:	Pumped 30SKS cement 400 # Hulls down 4 1/2 to 4350.												Sales Tax			
													Handling			
													Mileage			
													PUMP TRUCK CHARGE			
													Sub Total 934.00			
													Total			
													Floating Equipment & Plugs 4 1/2 Rubber 52 ⁰⁰			
													Squeeze Manifold			
													Rotating Head			
RECEIVED KANSAS CORPORATION COMMISSION NOV 30 2007 CONSERVATION DIVISION WICHITA, KS																
Signature David Brady												Tax 52.26				
												Discount (99.00)				
												Total Charge				

QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 1429

Date	11-14-07	Sec.	9	Twp.	31	Range	16	Called Out	On Location	Job Start	Finish
Lease	Hash Knife	Well No.	1-9		Location			29 miles west 10 North of Medicine		Comanche County	KS State

Contractor	Quality Well Service	Owner	To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.
Type Job	Plug	Charge To	Castelli Exploration
Hole Size	T.D.	Street	
Csg.	4 1/2	Depth	
Log. Size		Depth	
Drill Pipe		City	State
Log		The above was done to satisfaction and supervision of owner agent or contractor	
Cement Left in Csg.		Shoe Joint	
Press Max.		Minimum	
Meas Line		Displace	
Perf			

EQUIPMENT		Amount Ordered	220 180 SKS 60/40 4% gel.
		Consisting of	
Pumptrk	6 No. Cementer David Helper	Common	132 @ 11 ⁰⁰ 1452 ⁰⁰
Bulktrk	3 No. Driver Rich Driver	Poz. Mix	88 @ 6 ⁰³ 532 ⁴⁰
Bulktrk	No. Driver Dean Driver	Gel.	18 gel. 24 @ 17 ⁰⁰ 408 ⁰⁰

JOB SERVICES & REMARKS		Chloride	H @ 25 ⁰⁰	
Pumptrk Charge	2nd Day plug	Hulls	414 tipped plug	100 ⁰⁰
Mileage				
Footage				
Total				350 ⁰⁰

Remarks:	Sales Tax
1 st 1000 15 gel 59 SKS	Handling 248 @ 190 471 ⁹⁰
2 nd 320 80 SKS	Mileage 8¢ per sk per mile 773 ⁷⁶
3 rd 40' to surface. 40 SKS	39 miles
Tapped off with 20 SKS	Sub Total 350.00
	PUMP TRUCK CHARGE Total
	Floating Equipment & Plugs 4 1/2 Rubber 52 ⁰⁰
	Squeeze Manifold
	Rotating Head
	Tax 219.39
	Discount (414.00)
	Total Charge 3944.7

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 30 2007

CONSERVATION DIVISION
WICHITA, KS

X Signature David Beachy