

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc.
Address: P. O. Box 783188
Phone: (316) 691-9500 Operator License #: 4767
Type of Well: SWD Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11/12/2007 (Date)
by: Bruce Basye (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Cedar Hills Depth to Top: 1600' Bottom: 1630' T.D. 1885'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 065-00368-0001
Lease Name: Montgomery Area SWD
Well Number: 1
Spot Location (QQQQ): _____ - NW - NW - NE
330 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 8 Twp. 8 S. R. 23 East West
County: Graham
Date Well Completed: 04/12/1982
Plugging Commenced: 11/09/2007
Plugging Completed: 11/12/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Cedar Hills	Water	1600'	1630'	8.625"	165'	-0-
				4.50"	1855'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing down to 1650". Pumped 50 sx 60/40 Pozmix w/ 4% gel + 150 hulls. Pulled tubing up to 800'.
Pumped 65 sx 60/40 Pozmix w/ 4% gel + 200 hulls. Pulled tubing out of hole. Topped casing off with 15 sx 60/40 Pozmix w/ 4% gel.
Shut in at 350#. Pumped 5 sx 60/40 Pozmix w/ 4% gel down annulus. Plugging complete at 12:15 p.m. with
verbal approval by Bruce Basye with the KCC (not witnessed by KCC due to observation of Veteran's Day)

Name of Plugging Contractor: Allied Cementing License #: 9996 KCCPRT
Address: P. O. Box 31 Russell, KS 67665

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 30 2007

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.
State of Kansas County, Sedgwick

CONSERVATION DIVISION
WICHITA, KS

Peter J. Fiorini - employee of Ritchie Exploration, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____
(Address) P. O. Box 783188 Wichita, KS 67278-3188

DEBRA K. PHILLIPS
Notary Public - State of Kansas
My Appt. Expires 5-4-11

SUBSCRIBED and SWORN TO before me this 27th day of November, 20 07
My Commission Expires: 5-4-11
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

ALLIED CEMENTING CO., INC. 28771

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Oakley, KS

DATE <u>11-12-07</u>	SEC <u>8</u>	TWP. <u>85</u>	RANGE <u>23w</u>	CALLED OUT	ON LOCATION <u>10:00am</u>	JOB START	JOB FINISH
LEASE AREA <u>Montgomery</u>	WELL # <u>5WD #1</u>	LOCATION <u>Hill City 3w-1w</u>	COUNTY <u>Graham</u>	STATE <u>KS</u>			
OLD OR NEW (Circle one)		<u>1/2" 5" w</u>					

CONTRACTOR Express Well Service OWNER Same

TYPE OF JOB <u>AWP</u>	CEMENT
HOLE SIZE _____ T.D. _____	AMOUNT ORDERED <u>165 60/40</u>
CASING SIZE <u>4 1/2</u> DEPTH _____	<u>4" 70 gel used 125 sks</u>
TUBING SIZE <u>2 3/8</u> DEPTH <u>1650'</u>	<u>500* hulls on side</u>
DRILL PIPE _____ DEPTH _____	COMMON <u>75 9X</u> @ <u>12.60</u> <u>945.00</u>
TOOL _____ DEPTH _____	POZMIX <u>50 26</u> @ <u>6.40</u> <u>320.00</u>
PRES. MAX _____ MINIMUM _____	GEL <u>40</u> @ <u>16.65</u> <u>666.00</u>
MEAS. LINE _____ SHOE JOINT _____	CHLORIDE _____ @ _____
CEMENT LEFT IN CSG. _____	ASC _____ @ _____
PERFS. _____	Hulls <u>70 25</u> @ <u>25.00</u> <u>1750.00</u>
DISPLACEMENT _____	_____ @ _____

EQUIPMENT

PUMP TRUCK CEMENTER Fuzzy
431 HELPER Kelly
BULK TRUCK
377 DRIVER Alvin
BULK TRUCK
_____ DRIVER _____

HANDLING 181 @ 1.90 343.90
MILEAGE 109.5 km @ 11.70 1270.30
TOTAL 2994.30

REMARKS:

50SK 1650' with 150* hulls
Pull 500 lbs and cement
to surface with 55SK + 200* hulls
5SK down ann with 300*
pressure. Fill 4 1/2 csg with
15SK cement shut in @ 350*
Press Job complete @ 12:15pm
Thanks Fuzzy crew

SERVICE

DEPTH OF JOB 1650'
PUMP TRUCK CHARGE 720.00
EXTRA FOOTAGE _____ @ _____
MILEAGE 70 @ 6.00 420.00
MANIFOLD _____ @ _____
_____ @ _____
_____ @ _____

CHARGE TO: Finch Exploration
STREET _____
CITY _____ STATE _____ ZIP _____

TOTAL 1140.00

PLUG & FLOAT EQUIPMENT

_____ @ _____
_____ @ _____
_____ @ _____
_____ @ _____
_____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
TOTAL CHARGE _____
DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Thomas Atkins

Thomas Atkins
PRINTED NAME

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 30 2007
CONSERVATION DIVISION
WICHITA, KS