

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-05997-00-00
Spot: NESWSESW Sec/Twnshp/Rge: 30-19S-10W
621 feet from S Section Line, 3603 feet from E Section Line
Lease Name: FRED STECKEL Well #: 1
County: RICE Total Vertical Depth: 3848 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3475		
SURF	10.38	165		<u>125.06</u>

Well Type: SWD UIC Docket No: D00222.0 Date/Time to Plug: 10/25/2007 9:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: RANDY GINEST Company: RAMA OPERATING Phone: (620) 546-5235

Proposed Plugging Method: 25 SXS @ 3250', PERFORATE AND PUMP 35 SXS AT 1275', AND 900'. PERFORATE AT 250' AND CIRCULATE CEMENT FROM 250' TO SURFACE.

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/25/2007 6:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

RAN TUBING TO 3250' AND PUMPED 100 SXS CEMENT, PULLED TUBING AND PERFORATED CSING AT 1275', 900' AND AT 250'. PUMPED 35 SXS AT 1275', PULLED TUBING TO 900' AND PUMPED 35 SXS. PULLED TUBING TO 250' AND PUMPED 105 SXS TO CIRCULATE TO SURFACE. TOP PLUG FELL AND REQUIRED ANOTHER 1 1/4 YDS. SLURRY MIX TO FILL TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3475	3842		

INVOICED
DATE 12-5-07
INV. NO. 2008060883

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 29 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: BASIC ENERGY SERVICES TICKET #17390. TOTAL = 275 SXS 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

Signed

Greg Eves

(TECHNICIAN)