

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20834-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 8-3S-41W
815 feet from S Section Line, 2105 feet from E Section Line
Lease Name: ZWEYGARDT Well #: 34-08
County: CHEYENNE Total Vertical Depth: 5500 feet

Operator License No.: 33019
Op Name: ROSEWOOD RESOURCES, INC.
Address: 2711 N HASKELL STE 2800 LB # 22
DALLAS, TX 75204

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	278		

178.75

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/20/2007 3:00 AM
Plug Co. License No.: 33532 Plug Co. Name: ADVANCED DRILLING TECHNOLOGIES LLC
Proposal Rcvd. from: TOM ROELFS Company: ADVANCED DRILLING TECHNOL Phone: (214) 756-6600

Proposed Plugging Method: Order 100 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 11/20/2007 6:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 2650' w/35 sxs.
2nd. Plug at 325' w/40 sxs.
3rd. Plug at 60' w/10 sxs.
Rathole with 15 sxs.

Perfs:

INVOICED
DATE 12-3-07
INV. NO. 2008060846

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 21 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: LONGHORN CEMENTING COMPANY

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

Form CP-2/3

NOV 20 2007

PIET