

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20527-00-00
Spot: E2NWSESW Sec/Twnshp/Rge: 3-33S-41W
981 feet from S Section Line, 3384 feet from E Section Line
Lease Name: BERRYMAN RICHFIELD UNIT Well #: 15-3 A
County: MORTON Total Vertical Depth: 5155 feet

Operator License No.: 32659
Op Name: PHOENIX PETROCORP, INC.
Address: 15700 CUSTER TRAIL
FRISCO, TX 75035

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2995		
COND	13.38	563		WITH 425 SX CMT
PROD	5.5	5149	0	WITH 300 SX CMT
SURF	8.625	1531		WITH 650 SX CMT

167.54

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/29/2007 10:00 AM

Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.

Proposal Rcvd. from: TERRY GORDON Company: PHOENIX PETROCORP Phone: (972) 529-2544

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/31/2007 10:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG AT 2995' WITH CIBP. 2ND PLUG TESTED CASING & FOUND HOLE AT 1845'. PULLED TBG & PACKER TO 970'. PUMPED 150 SX CMT & 80# HULLS THROUGH HOLES AT 1845'. 3RD PLUG WAIT ON CMT FOR 3 HOURS. TEST CSG & PERFORATE 5 1/2" @ 600'. CIRCULATED CMT TO SURFACE WITH 216 SX CMT. SDON. 4TH PLUG FILL CASING WITH 15 SX CMT. 5TH PLUG FILLED ANNULUS WITH 60 SX CMT.

Perfs:

INVOICED
DATE 12-5-07
INV. NO. 2008060880

RECEIVED
KANSAS CORPORATION COMMISSION


NOV 29 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED CLASS C CMT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01



Signed

[Handwritten Signature]

(TECHNICIAN)