

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-151-20851-00-01
 Spot: NWNWSW Sec/Twnshp/Rge: 19-27S-15W
2310 feet from S Section Line, 4950 feet from E Section Line
 Lease Name: FRUIT Well #: 3
 County: PRATT Total Vertical Depth: 4600 feet

Operator License No.: 5004
 Op Name: VINCENT OIL CORPORATION
 Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4408		
PROD	5.5	4599	2440	WITH 225 SX CMT 149.50
SURF	8.625	363		WITH 250 SX CMT

Well Type: EOR UIC Docket No: E27323.1 Date/Time to Plug: 10/31/2007 1:00 PM
 Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
 Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND BSCK TO 3750' & 5 SX CMT. PLUG AT 990' WITH 50 SX CMT. PLUG AT 390' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: LINDLEY REIMER WitnessType: COMPLETE (100%)
 Date/Time Plugging Completed: 10/31/2007 2:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PACKER LEFT IN HOLE AT APP. 4300'. SANDED BACK TO 3750' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 990' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4444	4448		
4321	4328		
3831	3852		
3800	3813		

INVOICED
 DATE 12-5-07
 INV. NO. 2008060885

RECEIVED
 KANSAS CORPORATION COMMISSION


NOV 29 2007

CONSERVATION DIVISION
 WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
 (TECHNICIAN)