

3 022510

15-001.23500.00.00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER 15-001-

SW,NW,SE 1/4 Sec/Twp/Rge S.33-T.25S.-R.18E.

1870 feet from south section line

2200 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 32642

Lease/Well# HUME NO.4

County ALLEN

Operator: ~~B & S PETROLIUM~~ Brown, Nicholas L.

Well Total Depth 850 feet

Name &amp; 712 NAVAHO ROAD 2481 110th St

Production Pipe: 2" Size Feet 850'

Address YATES CENTER KS. 66783 Topeka, KS 66749

Surface Casing: 6 1/4" Size Feet 20'

AB oil well ☒ Gas Well ☒ SWD Well/ Input Well

D &amp; A

Other well as hereinafter indicated:

Plugging Contractor: ~~B & S PETROLIUM~~ Brown, Nicholas L.

Lic. # 32642

Address: 712 NAVAHO ROAD, YATES CENTER, KANSAS 66783

Company to plug at: Hour: 1200P.M. Day: 24 Month: 10 2003

Plugging proposal received from: NICK BROWN

Company Name: B &amp; S PETROLIUM Phone: 620-496-6242

Were: THIS WELL CONSISTED OF 2" CASING TO 850' THAT HAD BEEN CEMENTED IN FROM

BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2" CASING FULL OF

CEMENT FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All ☒ PartTECHNICIAN  
None

Operations Completed: Hour: 12:40P.M. Day: 24 Month: 10 2003

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE

2" CASING. CEMENT WAS PUMPED INTO THE 2" CASING UNTIL THE WELL WOULD HOLD

PRESSURE. THE WELL WAS THEN SHUT IN AT 200P.S.I.. AN ESTIMATED 35 SACKS OF

CEMENT WERE PUMPED INTO THIS WELL.

Remarks:

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED

Signed:

Clayton P. Titel  
TECHNICIAN

NOV 03 2003

KCC WICHITA

JST