

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20854-00-00
Spot: W2NWSW Sec/Twnshp/Rge: 27-4S-35W
1908 feet from S Section Line, 204 feet from W Section Line
Lease Name: DEWEY-CURRY UNIT "A" Well #: 1-27
County: RAWLINS Total Vertical Depth: 2788 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	262		

90.61

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/30/2007 5:15 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: BERNIE MAYER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Order 100 sxs common - 2% cc.
Plugging Started experiencing lost circulation problems at 2275' - finally lost total returns at 2788'.
Method: Decided to plug and abandon well.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 11/30/2007 10:15 PM KCC Agent: HERB DEINES

Actual Plugging Report:

Ran drill pipe to 2100' - pumped 25 sxs cement.
Let set for three hours.
Re-established circulation - spotted 40 sxs cement - plug at 325'.
Last plug at 40' with 10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 12-17-07
INV. NO. 2008060909

RECEIVED
DEC 05 2007
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

