

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21681-00-00
Spot: SENENW Sec/Twnshp/Rge: 12-15S-27W
1150 feet from N Section Line, 2310 feet from W Section Line
Lease Name: CHENEY-GARVEY Well #: 1
County: GOVE Total Vertical Depth: 4280 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 209 | | |

139.10

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/23/2007 6:00 PM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: FRANK ROME Company: PALOMINO PETROLEUM, INC. Phone: (620) 566-7324

Proposed Plugging Method: Ordered 200 sxs 60/04 pozmix- 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS WitnessType: NONE
Date/Time Plugging Completed: 11/23/2007 7:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st. Plug at 1800' w/25 sxs.
2nd. Plug at 730' w/100 sxs.
3rd. Plug at 260' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 12-17-07
INV. NO. 2008060913

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 28 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed [Signature]
(TECHNICIAN)

PJT

NOV 26 2007