

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21381-00-01

Spot: NESWSWNE

Sec/Twnshp/Rge: 1-12S-25W

³⁰⁰² 3080 feet from S Section Line, 2200 feet from E Section Line

Lease Name: SCHIMKOWITSCH A P

Well #: 1 ERW

County: TREGO

Total Vertical Depth: 4200 feet

Operator License No.: 4767

Op Name: RITCHIE EXPLORATION, INC.

Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4197	0	w/200 sxs cmt
SURF	8.625	261	0	w/170 sxs cmt

136.50

Well Type: EOR

UIC Docket No: E23601.1

Date/Time to Plug: 11/27/2007 9:00 AM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: TOM

Company: RITCHIE EXPLORATION, INC.

Phone: (316) 691-9500

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 4% gel - 800# hulls.
CIBP 4085'. DV Tool at 2162' w/400 sxs.

Plugging Proposal Received By: MARVIN MILLS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/27/2007 12:15 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 2925' - pumped 90 sxs cement with 300# hulls.
Pulled tubing to 1925' - pumped 90 sxs cement with 300# hulls - cement circulated.
Pulled tubing out - tied onto top and squeezed 125 sxs cement with 100# hulls.
Max. P.S.I. 400#. S.I.P. 200#.
Dug out backside - found full of cement.

INVOICED
DATE 12-17-07
INV. NO. 2008060917

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 03 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #28783.

Plugged through: TBG

District: 04

Signed

Marvin Mills

(TECHNICIAN)

NOV 28 2007

