

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-21424-00-00

Spot: <sup>SW</sup> ~~SENWNWSW~~

Sec/Twnshp/Rge: 1-12S-25W

2237.2200 feet from S Section Line,

440 feet from W Section Line

Lease Name: SCHIMKOWITSCH C

LP165 Well #: 2-1

County: TREGO

Total Vertical Depth: 4160 feet

KCC  
PKT  
per  
oper  
CP-4

Operator License No.: 4767

Op Name: RITCHIE EXPLORATION, INC.

Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

| String | Size  | Depth (ft) | Pulled (ft) | Comments      |
|--------|-------|------------|-------------|---------------|
| PROD   | 5.5   | 4158       | 0           | w/200 sxs cmt |
| SURF   | 8.625 | 261        | 0           | w/170 sxs cmt |

135.20

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/27/2007 2:00 PM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: TOM

Company: RITCHIE EXPLORATION, INC.

Phone: (316) 691-9500

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 4% gel - 800# hulls.  
Casing leak deep.

Plugging Proposal Received By: MARVIN MILLS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 11/27/2007 6:00 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 2850' - pumped 90 sxs cement with 300# hulls.  
Pulled tubing to 1850' - pumped 90 sxs cement with 300# hulls.  
Pulled tubing to 950' - pumped 110 sxs cement with 100# hulls - cement circulated.  
Pulled tubing out - tied onto the 5 1/2" - squeezed with 115 sxs cement - went on vacuum - stopped.  
Topped off with 25 sxs cement.  
Tied onto the backside - pumped 5 sxs cement.  
S.I.P. 200#.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4068 | 4074 |      |          |

INVOICED  
DATE 12-17-07  
INV. NO. 200806091

RECEIVED  
KANSAS CORPORATION COMMISSION

DEC 03 2007

CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #28784.

Plugged through: TBG

District: 04

Signed

[Signature]  
(TECHNICIAN)

NOV 28 2007

DON E. PRATT  
P.O. BOX 370  
HAYS, KS 67601

#2-1 "C" SCHIMKOWITZ  
1-12-25W  
2200 FSL &  
440 FWL, SW/4

CONTR RED TIGER DRILLING CO. CTY TREGO

GEOL

FIELD ENGLEBERT

|   |   |   |   |   |
|---|---|---|---|---|
| - | - | - | - | - |
| - | - | - | - | - |
| - | - | - | - | - |
| - | - | - | - | - |
| - | - | - | - | - |

ELV 2547 KB SPD 2/9/84 CARD ISSUED 5/3/84 IP P 80 80 & 8 BWPD  
2544 GL LKC 4068-4074

| LOG     | Tops  | Depth/Datum |
|---------|-------|-------------|
| HEEB    | ..... | 3862-1315   |
| TOR     | ..... | 3883-1336   |
| LKC     | ..... | 3898-1351   |
| BENCH I | ..... | 4068-1521   |
| BKC     | ..... | 4147-1600   |
| RTD     | ..... | 4163-1616   |

API 15-195-21, 424  
8 5/8 " 261 / 170SX; 5 1/2 " 4158 / 600SX  
DST (1) 4055-4078 (LKC) / 30-45-45-90 REC 248 MDY OIL,  
124' MCO, SIP 459-459# / FP 39-98 / 108-166#  
MICT - CO, PF (LKC) 4068-74, W/4 SP, AC 2500G (15% SGA),  
SWB DWN, SO, POP, P 80 80 & 8 BWPD, (GR 37.8%), 2/26/84

COPYRIGHT 1983  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS