

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20545-00-00
Spot: NWSENE Sec/Twnshp/Rge: 5-27S-13W
4570 feet from S Section Line, 610 feet from E Section Line
Lease Name: CHANDLER Well #: 1
County: PRATT Total Vertical Depth: 3330 feet

Operator License No.: 9232
Op Name: TIMBERLINE OIL & GAS CORPORATIO
Address: 4000 PENROSE PL
RAPID CITY, SD 57702

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3325	1819	WITH 300 SX CMT
SURF	10.75	409		WITH 325 SX CMT <u>108.23</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2007 1:15 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3110' & 5 SX CMT. PLUG AT 880' WITH 50 SX CMT. PLUG AT 440' WITH 75 SX CMT. PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/20/2007 2:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3050' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 880' WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 440' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.


Perfs:

Top	Bot	Thru	Comments
3238	3240		
3193	3200		
3173	3178		
3161	3163		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)