

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02342-00-00
Spot: NESWSW Sec/Twnshp/Rge: 31-10S-17W
990 feet from S Section Line, 4290 feet from E Section Line
Lease Name: RIDLER A Well #: 3
County: ROOKS Total Vertical Depth: 3596 feet

Operator License No.: 30537
Op Name: VENTURE RESOURCES, INC.
Address: PO BOX 101234
DENVER, CO 80250

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3594	0	w/100 sxs cmt
SURF	10.75	1322	0	w/400 sxs cmt

116-87

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/27/2007 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOHN CROWLEY Company: VENTURE RESOURCES, INC. Phone: (785) 731-5073

Proposed Plugging Method: Ordered out 750 sxs 60/40 pozmix - 4% gel with 600# hulls.
Ordered 250 sxs common cement - 3% cc with 1000# hulls.
01/31/1951 Open hole 3594'-3596'. Bridge Plug at 3499'.
02/17/1963 LKC Perfs: 3479'-3488'; 3461'-3464'; 3439'-3445'; 3420'-3428'.
Cleaned out to 2950'
Lost hole - decided to P/A.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/27/2007 4:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Perforated at 1300' - 2 holes.
Ran tubing to 2926'. Swift Services pumped 100 sxs common with 3% cc and 250# hulls.
Pulled tubing to 2326'. Shut down one hour.
Pumped 150 sxs common with 3% cc and 350# hulls.
Pulled tubing to 1226'. Shut down one hour.
Ran tubing back to 1750'. Tagged cement. Shut in one hour.
Tubing at 1730'. Swift Services pumped 135 sxs 60/40 pozmix - 4% gel with 300# hulls.
Good circulation.
Pulled tubing to 865'. Swift Services pumped 100 sxs 60/40 pozmix - 4% gel w/150# hulls cwc.
PTOH. Topped 7" casing with 40 sxs. Hole full.
Pumped 80 sxs 60/40 pozmix - 4% gel with 100# hulls down 10 3/4".
Max. P.S.I. 500#. S.I.P. 500#.

INVOICED
DATE 12-17-07
INV. NO. 2008060920

RECEIVED
DEC 05 2007
KCC WICHITA

Remarks: SWIFT SERVICES, INC. - J&M TANK SERVICE.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

103

Form CP-2/3

NOV 30 2007

REPUBLIC NATURAL GAS CO. #3 RIDLER A 31-10-17W 23
 NE SW SW

Contr. _____ ROOKS _____ Coun _____
 E. 2043 Comm. _____ Comp. _____ 2-9-51 IP 113 BOPD
 PHY POT

Tops	Depth	Datum	Casing
ANH	1341	+ 702	10" 1321 7" 3594
HEEB	3222	- 1179	
LANS	3260	- 1217	
CONG	3512	- 1469	
SIMP	3571	- 1528	
ARB	3593	- 1550	
T.D.	3596	- 1563	

BURNETT POOL

+	+	+	+
+	+	+	+
+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS