

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-13132-00-01  
Spot: NESWNE Sec/Twnshp/Rge: 12-25S-13W  
1800 feet from N Section Line, 1800 feet from E Section Line  
Lease Name: N. LEESBURG UNIT Well #: 204  
County: STAFFORD Total Vertical Depth: 4221 feet

Operator License No.: 33608  
Op Name: W.D. SHORT OIL CO., LLC  
Address: 102 S RIVER RD PO BOX 729  
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	4219	0	WITH 250 SX CMT
SURF	10.75	254		WITH 225 SX CMT <b>137.18</b>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/26/2007 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/26/2007 12:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SQUEEZED AT 334-428' W/250 SX CMT CIRCULATED TO SURFACE. RAN TUBING TO 3600' & PUMPED 300# HULLS & 75 SX CMT. PERFORATED 7" @ 760'. PULLED TUBING TO 760'. PUMPED 150 SX CMT. CIRCULATED CMT TO SURFACE UP 7". PULLED TUBING OUT OF HOLE. TOPPED OFF 7" WITH 15 SX CMT. VISUALLY INSPECTED 7" X 10 3/4" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
3755	3762		
3724	3733		
3708	3716		
3624	3629		


INVOICED  
DATE 12-17-07  
INV. NO. 20080609021

RECEIVED  
KANSAS CORPORATION COMMISS  
  
DEC 04 2007  
  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

District: 01



Signed Richard M. Lacey  
(TECHNICIAN)