

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-01901-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 6-10S-25W  
3630 feet from S Section Line, 990 feet from E Section Line  
Lease Name: GRASHER BRUNGARDT Well #: B-3  
County: GRAHAM Total Vertical Depth: 4011 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4009	0	50 SX
SURF	8.625	200	0	125 SX

\$ 130.36

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/29/2007 10:00 AM  
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.  
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 240 sxs 60/40 pozmix - 4% gel - 500# hulls - 16 sxs gel.  
CIBP at 4000'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/29/2007 1:00 PM KCC Agent: MARVIN MILLS

**Actual Plugging Report:**

Tied on the 4 1/2" - pumped 150 sxs cement.  
Pumped 13 sxs gel - pumped 90 sxs cement with 500# hulls - went on strong vacuum.  
Let set 4 hours.  
Topped off with 45 sxs cement - full.  
Tied on backside - full.  
S.I.P. 1000#.

**Perfs:**

Top	Bot	Thru	Comments
3834	4011		

**INVOICED**  
DATE 12-14-07  
INV. NO. 2008060900

**RECEIVED**  
**DEC 05 2007**  
**KCC WICHITA**

Remarks: LEASE ALSO KNOWN AS BRUNGARDT #3 (GRA-SHER B-3). ALLIED CEMENTING COMPANY-TICKET #2808.

Plugged through: CSG

District: 04

110

Signed \_\_\_\_\_

*Marvin Mills*

(TECHNICIAN)

DEC 03 2007

PCT

KCC

15-065-01901-00-00

6-10-25W  
NW SE NE

#3 BRUNGARDT


THE KIMBARK COMPANY

Contr. LOGAN DRLG GRAHAM County

E257RB Comm. 5-15-59 IP 81 BOPD  
PHY POT

Tops	Depth	Datum	Casing
TOR	3788	-1231	8" 200 4 1/2" 5" 4009
KC	3800	-1243	CO: ACID 500: 8 BO & 1 SMPH: PB 3998: PERF 3988-91: ACID 500: 10 BOPH: CO: DD 4011
TD	4011	-1454	

GRA-SNER POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS