

15-065-01905-00-03

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-01905-00-01  
Spot: NWNESESW Sec/Twnshp/Rge: 6-10S-25W  
2312 feet from S Section Line, 3070 feet from E Section Line  
Lease Name: GRA-SHER Well #: M1  
County: GRAHAM Total Vertical Depth: 4037 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4020		
PROD	4.5	4032	0	600
SURF	8.625	193	0	175 SX CMT.

\$131.20

Well Type: EOR UIC Docket No: E21996.2 Date/Time to Plug: 11/29/2007 2:00 PM  
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.  
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 285 sxs 60/40 pozmix - 4% gel - 600# hulls.  
CIBP at 4020' & 4005'.  
1261' of 2 3/8" tubing - stuck in the hole.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/29/2007 5:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 2589' - pumped 285 sxs cement with circulation of water - no cement - ran out of cement - ordered more cement.  
Pulled tubing to 1470' - pumped 125 sxs cement with 500# hulls - circulated - good cement.  
Pulled tubing out - tied on 4 1/2" - topped off with 20 sxs.  
Tied on backside - squeezed with 50 sxs.  
Max. P.S.I. 200#.

Perfs:

Top	Bot	Thru	Comments
3988			KC
3855	4013		L-KC

INVOICED

DATE 12-14-07  
INV. NO. 2008060900

RECEIVED  
DEC 05 2007  
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS MADER #1. ALLIED CEMENTING COMPANY-TICKET #28088.

Plugged through: TBG

District: 04

Signed *Marvin Mills*  
(TECHNICIAN)

DEC 03 2007

*PKT*

KCC

PAGE 02

15-065-01965-00-01  
6-10-25W  
NE NE SW  
GRAHAM-SHER M-1  
#1, MADER

KIMBARK OIL CO

LOGAN ORLG

GRAHAM County

E 2577RB Comm 11-6-59 Comp IP 90 BOPD  
PHY POT

Tops	Depth	Datum
HEEB	3789	-1212
TOR	3809	-1232
LANS	3824	-1247
TD	4037	-1460

Casing  
8" 195  
4" 4032  
DST 3840-65/1 HR, G/25", 1620' O,  
90' W, BHP 1105#  
DST 3957-72/1 HR, 3480' G, 180'  
OCM, 720' O, 1380' W, BHP 1270#  
DD 4037: WTR: PB 4020: PERF 8/  
4010-13: ACID 500: WTR: PB 4005  
PERF 3995-97: WTR: SQZ: PB: PERF  
3952-64: 2100' O & WIH/1 HR: SWB 10  
BO & 10. BWPH: PMP 96 BO & 50% W/24

	HR

GRAHAM-SHER POOL

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS