

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05958-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 28-11S-17W
4290 feet from S Section Line, 2310 feet from E Section Line
Lease Name: BEMIS SHUTTS A Well #: 8
County: ELLIS Total Vertical Depth: 3411 feet

Operator License No.: 33263
Op Name: BOWMAN, WILLIAM F. DBA THE BILL
Address: 2640 WRD
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	16	32		
PROD	6	3403	0	w/unknown sxs cmt
SURF	10.75	1121	0	w/unknown sxs cmt

110.86

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2007 10:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: BILL BOWMAN Company: THE BILL BOWMAN OIL COMPAN Phone: (785) 885-4830

Proposed Plugging Method: Ordered 675 sxs 60/40 pozmix - 4% gel - 3% cc - 1300# hulls.
Hole full of drilling mud.
Perf at 1140' and 600'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/20/2007 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 2027' - pumped 40 sxs cement with 350# hulls.
Pulled tubing to 1725' - pumped 30 sxs cement with 200# hulls.
Pulled tubing to 1175' - pumped 40 sxs cement with 200# hulls.
Pulled tubing to 625' - waited one hour - pumped 315 sxs cement with 550# hulls - good circulation of cement out the backside and the casing.
Pulled tubing out - tied on casing and squeezed with 10 sxs cement - full.

Perfs:

INVOICED
DATE 12-14-07
INV. NO. 2008060901

RECEIVED
DEC 05 2007
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #28089.
Plugged through: TBG

District: 04

10

Signed Marvin Mills
(TECHNICIAN)

DEC 03 2007

PVT

THE TEXAS CO

#A-8 BEMIS

28-11-17W
SW NW NE

Contr.

ELLIS County

TD 8-4-37

E 1902 Comm 6-30-37 Comp 8-4-37 IP

2754 BOFD

Tops	Depth	Datum	Casing
ANH	1114		10" 1121
			6" 3403
ARB	3402		
TD	3411		

Pay 3402-11
FU 3000' OIL/3 hrs

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS