


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 35 Twp. 19S Rge. _____ (E) 20 (W)
Location as "NE/CNW/SW" or footage from lines NE NW SW
Lease Owner Chief Drilling Co., Inc.
Lease Name ARMBRISTER Well No. 1
Office Address _____
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 9/11 1965
Application for plugging filed 9/11 1965
Application for plugging approved 9/11 1965
Plugging commenced 9/11 1965
Plugging completed 9/11 1965
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty - Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3736 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	200	8-5/8"	200	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Wooden plug set @ 540'
Mixed 20 sacks cement through drill pipe
Wooden plug set @ 190'
Mixed 20 sacks cement through drill pipe
Hulls and wooden plug set @ 40'
Mixed 10 sacks cement through drill pipe

RECEIVED
STATE CORPORATION COMMISSION

SEP 15 1965
09-15-1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.
Address Box 797 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. CHIEF DRILLING CO., INC.

(Signature) V. Richard Hoover
Box 797 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of September, 1965

My commission expires Jan. 26, 1967
Carmen R. Cook
Carmen R. Cook, Notary Public.

15-163-30132-00-00

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas

ARMBRISTER #1 10s-
NE NW SW Sec. 35-19S-20W
Rooks County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 9-3-65
Completed: 9-11-65

Casing Record: 8-5/8" @ 200' w/150 sacks Sunset & 2 sacks Gel.

DRY & ABANDONED

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Shale	0	199	2131 Gr.
Clay & Shale	199	760	2133 D.F.
Shale	760	1050	2136 K.B.
Sand	1050	1255	
Shale, Shells & Red Bed	1255	1570	
Anhydrite	1570	1612	
Shale	1612	1730	
Lime & Shale	1730	3177	
Lime	3177	3390	
Shale & Lime	3390	3430	
Lime	3430	3641	
Lime & Shale	3641	3685	
Conglomerate	3685	3736	
Total Depth	3736		

<u>FORMATION TOPS</u>	
Anhydrite	1570 + 566
Topeka	3177 -1041
Heebner	3390 -1254
Toronto	3413 -1277
Lansing-Kansas City	3430 -1294
Base Kansas City	3641 -1505
Conglomerate	3685 -1549
Simpson	3732 -1596
Total Depth	3736 -1600

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NE NW SW Section 35-19S-20W, Rooks County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 14th day of September, 1965.

Carmen R. Cook
Carmen R. Cook, Notary Public

My commission expires: Jan. 26, 1967.

RECEIVED
STATE CORPORATION COMMISSION

SEP 15 1965
09-15-1965
CONSERVATION DIVISION
Wichita, Kansas