


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-163-03116-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County, Sec. 35 Twp. 10S Rge. 20W (E) (W)
Location as "NE/CNW/SW" or footage from lines E/2 NE NW
Lease Owner El Dorado Refining / Sierra Petroleum Co., Inc.
Lease Name Armbrister A Well No. 2
Office Address Russell, Kansas / 420 W. Douglas Ave., Wichita, Ks
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 6/18/57 19
Application for plugging filed 6/17/57 19
Application for plugging approved 6/17/57 19
Plugging commenced 6/18/57 19
Plugging completed 6/18/57 19
Reason for abandonment of well or producing formation well dry

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3775 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	243.50	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud from 3775 up to 235. Set bridge with hulls wood plug and 20 sacks cement through drill pipe. Filled hole with heavy mud up to 40' with 1/2 sack hulls, wood plug and 10 sacks cement to cellar 0. Job complete 1:45 p.m. 6/18/57

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1957
06-21-1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sierra Petroleum Co., Inc.
Address 420 W. Douglas Ave., Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. T. Honaker (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) C. T. Honaker

SUBSCRIBED AND SWORN TO before me this 20th day of June, 19 57

My commission expires 1-30-61
Margie Cooper Notary Public.

PLUGGING
FILE SEC. 35 T. 10 R. 20W
BOOK PAGE 22 LINE 6

15-163-03116-00-00

El Dorado Refining Co - Owner

Sierra Petroleum - Contr.

ARMBRISTER A #2

E/2 NE NW Sec. 35-10S-20W
Rooks County, Kansas

Total Depth: 3775

Elev: 2187 KB

Comm: 6/7/57
Comp: 6/18/57

Casings:

8 5/8" @ 243.50

with 135 sacks CC

FORMATION	DEPTH
Sand - Clay	120
Shale, shells & pyrite	242
Shale & shells	710
Shale, sand & pyrite	1080
Sand & shale	1250
Shale & sand streaks	1365
Red bed	1610
Anhydrite	1650
Shale & shells	1980
Salt & shale	2140
Shale & lime	3475
Lime	3654
Lime Chert	3714
Conglomerate	3750
Simpson	3769
Arbuckle	3775

Tops:	DEPTH
Anhydrite	1610
Topeka	3207
Heebner	3419
Toronto	3444
Lansing K. C.	3457
Base Kansas City	3667
Conglomerate	3703
Simpson	3742
Arbuckle	3769

STATE OF KANSAS)
) ss:
 COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. P. Honaker

Subscribed and sworn to before me this 20th day of June, 1957.

Margie Casper
 Notary Public

My commission expires: 1-30-61.

RECEIVED
 STATE CORPORATION COMMISSION

JUN 21 1957
 06-21-1957
 CONSERVATION DIVISION
 Kansas

PLUGGING			
FILE	SEC. 35	T. 10	R. 20W
BOOK	PAGE 22	LINE	6