

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 28 2007
CONSERVATION DIVISION
WICHITA, KS

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Cherokee Wells, LLC.

Address: 7049 1400 Road, P.O. Box 296, Fredonia, KS 66736

Phone: (620) 378-3650 Operator License #: 33539

Type of Well: Gas Storage Field Monitoring Well Docket #: N/A
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 10/8/07 (Date)

by: Alan Dunning (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

Cherryvale S.S. Depth to Top: 230' Bottom: 249' T.D. 249'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 205-19346 - 00-01

Lease Name: G.A. Charlen

Well Number: 010

Spot Location (QQQQ): NE - NE - SW - NE

1369 Feet from ☒ North / ☐ South Section Line

1429 Feet from ☒ East / ☐ West Section Line

Sec. 17 Twp. 29 S. R. 15 ☒ East ☐ West

County: Wilson

Date Well Completed: Approx. 7/27/1949

Plugging Commenced: 11/9/07

Plugging Completed: 11/9/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Cherryvale S.S.	Gas	10'	Surface	8.625"	10'	N/A
		230'	Surface	2.0"	230'	N/A

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RIH with 1" poly pipe to fill in hole at 218'. Mix and pump 20 sacks of 60/40 poz with 2% gel. Good cement returns to surface. Let set, then topped off with cement. Cut off 8.625" surface casing and 2" tubing 4' below ground level.

Name of Plugging Contractor: Consolidated ~~Oil~~ Consolidated Oil Well Services LLC License #: 33961

Address: _____

Name of Party Responsible for Plugging Fees: Cherokee Wells, LLC.

State of KS County, Wilson, ss.


Jeff Morris

(Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the leg of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Jeff Morris

(Address) 7049 1400 Road, P.O. Box 296, Fredonia, KS 66736



SUBSCRIBED and SWORN TO before me this 26 day of November, 20 07

Tracy Miller
Notary Public

My Commission Expires: 12/1/2010

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

TREATMENT REPORT & FIELD TICKET
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
11-9-07	3094	CHARLEN #010	17	29S	15E	WILSON
CUSTOMER Cherokee Wells, LLC			<div>Fredonia Storage Field</div>			
MAILING ADDRESS PO Box 2916						
CITY Fredonia	STATE KS	ZIP CODE 66136				

TRUCK #	DRIVER	TRUCK #	DRIVER
445	Justin		
502	Jerrid		

JOB TYPE <u>PTA</u>	HOLE SIZE _____	HOLE DEPTH _____	CASING SIZE & WEIGHT _____
CASING DEPTH _____	DRILL PIPE _____	TUBING <u>2"</u>	OTHER _____
SLURRY WEIGHT _____	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING _____
DISPLACEMENT _____	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____

REMARKS: Safety Meeting: RAN 1" Continuous BLACK PVC Pipe down 2" Tubing to 218'.
BREAK Circulation w/ Fresh water. MIXED 60/40 Pozmix Cement w/ 4% Gel
until we had Good Cement to Surface. Shut down. Pull out 1" PVC. Top of
Tubing w/ Cement. 20 sks Total to Plug well. Job Complete. Rig down.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405 A	1	PUMP CHARGE	550.00	550.00
5406	40	MILEAGE 1 st well of 3	3.30	132.00
1131	20 SKS	60/40 Pozmix Cement	9.80	196.00
1118 A	70 *	Gel 4%	.15 *	10.50
5407	- 86 Ton	Ton Mileage BULK TRUCK	MIC	285.00
THANK YOU			Sub Total	1173.50
6.3%			SALES TAX	13.01
218213			ESTIMATED TOTAL	1186.51

AUTHORIZATION Witnessed By James

TITLE

DATE _____