

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

RECEIVED  
NOV 28 2007  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KS

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Cherokee Wells, LLC.  
Address: 7049 1400 Road, P.O. Box 296, Fredonia, KS 66736  
Phone: (620) 378-3650 Operator License #: 33539  
Type of Well: Gas Docket #: N/A  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)* *(If SWD or ENHR)*  
The plugging proposal was approved on: Approx. 11/6/07 (Date)  
by: Alan Dunning (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
N/A Depth to Top: N/A Bottom: N/A T.D. N/A  
N/A Depth to Top: N/A Bottom: N/A T.D. N/A  
N/A Depth to Top: N/A Bottom: N/A T.D. N/A

API Number: 15 - 205-27307-0000  
Lease Name: Craig  
Well Number: A-1  
Spot Location (QQQQ): C - NE - NW - NW  
330 Feet from  North /  South Section Line  
990 Feet from  East /  West Section Line  
Sec. 10 Twp. 29 S. R. 14  East  West  
County: Wilson  
Date Well Completed: Not Completed - OH  
Plugging Commenced: 11/9/07  
Plugging Completed: 11/10/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Plattsburg L.S.	Brine	44.2'	Surface	8.625"	44.2'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


11/9/07 - TIH to driller TD of 405' with 2.375" EUE tubing. Pump 140 sacks of 60/40 poz mix with 2% gel. Good cement returns to surface.  
11/10/07 - Cement column had fallen. TIH with 2.375" EUE tubing to 190'. Mix and pump 75 sacks of class A cement with 2% gel and 3% caciz. Wait 1 hour and top off. Cut off 8.625" surface casing 4' below ground level.

Name of Plugging Contractor: Consolidated Oil Well Services LLC License #: 33961  
Address: \_\_\_\_\_

Name of Party Responsible for Plugging Fees: Cherokee Wells, LLC.  
State of KS County, Wilson, ss.

Jeff Morris (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above described well is as filed, and the same are true and correct, so help me God.

(Signature) Jeff Morris  
(Address) 7049 1400 Road, P.O. Box 296, Fredonia, KS 66736



My Commission Expires: 12/1/2010  
Subscribed and SWORN TO before me this 26 day of November, 20 07  
Tracy Miller Notary Public

