

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior Inc.
 Address: P.O Box 399, Garden City Ks. 67846
 Phone: (620) 272-1023 Operator License #: 4058
 Type of Well: Oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)
 The plugging proposal was approved on: 11/5/07 (Date)
 by: Marvin Mills (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Lansing/KC Depth to Top: 3829' Bottom: 3943' T.D. 4070'
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-179-20877-00-00
 Lease Name: Bittel E
 Well Number: #E-1 Per CP 213 KCC PKT
 Spot Location (QQQQ): C - NW - NE - NE
4950' Feet from North / South Section Line
990' Feet from East / West Section Line
 Sec. 11 Twp. 10S S. R. 26W East West
 County: Sheridan
 Date Well Completed: 1/1/87
 Plugging Commenced: 11/5/07
 Plugging Completed: 11/5/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	207'	85/8	207'	0
		surface	4068'	51/2	4068'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Riun tbg to 2995', Swift hooked up to tbg amd pumped 85sx 60/40 posw/300# hulls. Pulled tbg to 1900', Swift hooked to tbg, pumped 100sx 60/40 pos w/ 200# hulls. Pulled tbg to 1000'. swift hooked up to tbg, pumped 100sx 60/40 pos w/200# hulls, pulled tbg to 500'. Swift hooked up to tbg, pumped 100sx 60/40 poss. Pulled tbg. Hooked up to 51/2 and topped off. Hooked up to annulus pumped 25sx. Hooked up to 51/2 pumped 20sx.

Name of Plugging Contractor: Express Well Service & Supply Inc License #: 32382
Swift Services Inc License #: 6426 CP 213
 Address: P.O. box 466 Ness City Kansas 67560

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: American Warrior Inc.
 State of Kansas County, Finney, ss.
Joe smith (Employee of Operator) or (Operator) on above-described well, being first duly

NOV 28 2007

CONSERVATION DIVISION
WICHITA, KS

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

ERICA KUHLMEIER
Notary Public - State of Kansas
My Appt. Expires 09-12-09

(Signature) [Signature]
 (Address) P.O. Box 399 Garden City Kansas 67846

SUBSCRIBED and SWORN TO before me this 27 day of November, 20 07
[Signature] My Commission Expires: 09-12-09
 Notary Public

[Handwritten Signature]