

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
**Type or Print on this Form**  
Form must be Signed  
All blanks must be Filled

Lease Operator: Rupe Oil Comapny  
 Address: P.O. Box 783010, Wichita, KS 67278  
 Phone: (316) 689-3520 Operator License #: 5047  
 Type of Well: Oil/Gas KCCPWT Per CP213 Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: 09/18/2007 (Date)  
 by: Eric Mac Cleren (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
 \_\_\_\_\_ Depth to Top: 3776 Bottom: 3788 T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: 2802 Bottom: 2809 T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 151-22226-000  
 Lease Name: Perry  
 Well Number: 1-32  
 Spot Location (QQQQ): C - NW - NW - \_\_\_\_\_  
660 Feet from  North /  South Section Line  
660 Feet from  East /  West Section Line  
 Sec. 32 Twp. 29 S. R. 12  East  West  
 County: Pratt  
 Date Well Completed: 09/09/2005  
 Plugging Commenced: 09/19/2007  
 Plugging Completed: 09/20/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	285	None
				5 1/2	3851	2400

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

9-19 - MIRU, Log Tech set CIBP at 2750, spot 2 sacks portland with dump bailer, rig up casing tools, stretch pipe  
9/20 - cut casing off at 2400, lay down casing, run 2 3/8 tubing to 760, Allied load hole with 10 sacks gel, pump 50 sacks  
60/40 POZ 4% gel, pull tubing to 320, spot 50 sacks, pull to 60, load to surface, 9-21 - top surface 160' redi mix

Name of Plugging Contractor: Clarke Corporation License #: 5105  
 Address: P.O. Box 187, Medicine Lodge, KS 67104


**RECEIVED**  
**KANSAS CORPORATION COMMISSION**  
**NOV 21 2007**

Name of Party Responsible for Plugging Fees: Rupe Oil Comapny  
 State of Kansas County, Barber, ss.

CONSERVATION DIVISION  
WICHITA, KS

John Gwinford Mark Morgenstern (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mark Morgenstern  
 (Address) P.O. Box 187, Medicine Lodge, KS 67104



SUBSCRIBED and SWORN TO before me this 16 day of Nov, 2007  
Glenda Morrison My Commission Expires: 11/3/10  
 Notary Public

*[Handwritten initials]*