

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Woolsey Operating Company, LLC
 Address: 125 N. Market, Wichita, KS 67202
 Phone: (620) 886-5606 Operator License #: 3487 33168
 Type of Well: D & A Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 9/24/2007 (Date)
 by: Steve Vang (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: 3986 Bottom: 3994 T.D. _____
 _____ Depth to Top: 4000 Bottom: 4020 T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 191-22454-0000
 Lease Name: Stephens Trust
 Well Number: #1
 Spot Location (QQQQ): NE - NE - NE -
530 Feet from North / South Section Line
970 Feet from East / West Section Line
 Sec. 3 Twp. 33 S. R. 4 East West
 County: Sumner
 Date Well Completed: 7/06/2005
 Plugging Commenced: 09/25/2007
 Plugging Completed: 09/27/2007

KCC Pkt per CPB

KCC Pkt per CPB

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
			319	10 3/4		None
			4519	4 1/2		3400

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set cast iron bridge plug at 3936, spot 2 sacks common cement on bridge plug with dump bailer, cut casing at 3400', pull and lay down 4 1/2 casing, run tubing back in to 750', spot 100 hulls, 10 gel, 35 sacks of 60/40 POZ/ 4 % gel, pull tubing up to 370', circulate cement to surface, 165 sacks POZ 4% gel, Measure surface at 260', ready mix to surface


Name of Plugging Contractor: Clarke Corporation License #: 5105
 Address: P.O. Box 187, Medicine Lodge, KS 67104

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 21 2007
 CONSERVATION DIVISION
 WICHITA, KS

Name of Party Responsible for Plugging Fees: Woolsey Operating Company, LLC
 State of Kansas County, Barber, ss.

Mark Morgenstern (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mark Morgenstern
 (Address) P.O. Box 187, Medicine Lodge, KS 67104



SUBSCRIBED and SWORN TO before me this 16 day of November, 20 07
Glenda Morrison My Commission Expires: 11/30/12
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten signature]