

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Red Cedar Oil  
 Address: P.O. Box 221, Medicine Lodge, KS 67104  
 Phone: (620) 886-3951 Operator License #: 30991  
 Type of Well: Gas Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: 10/04/2007 (Date)  
 by: Steve Durant (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
 \_\_\_\_\_ Depth to Top: 4861 Bottom: 4866 T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: 4845 Bottom: 4850 T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: 4804 Bottom: 4809 T.D. \_\_\_\_\_

API Number: 15-007-20662-00-00  
 Lease Name: Rusk C KCC  
 Well Number: 6-1 Per CP 2/3 PPT  
 Spot Location (QQQQ): NW - SW - NE - SE KCC PPT  
990 Feet from  North /  South Section Line  
2310 Feet from  East /  West Section Line  
 Sec. 6 Twp. 32 S. R. 15  East  West  
 County: Barber KCC KB DMS  
 Date Well Completed: 09/09/1978 Per CP 2/3  
 Plugging Commenced: 10/04/2007 PPT  
 Plugging Completed: 10/09/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
			435	8 5/8	435	None
			4909	4 1/2	4909	2800

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set cast iron bridge plug at 4715, spot 2 sacks common cement on bridge plug with dump bailer, cut casing at 3200', 3100', 3000', 2900', 2800', came free, pull and lay down 2800' of 4 1/2 casing, run tubing back in to 1200', spot 300 hulls, 10 gel, 50 sacks 60/40 POZ 4% gel, pull up to 450', spot 50 sacks 60/40 POZ, came up to 60', circulate to surface with 20 sacks

Name of Plugging Contractor: Clarke Corporation License #: 5105  
 Address: P.O. Box 187, Medicine Lodge, KS 67104


**RECEIVED**  
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Red Cedar Oil  
 State of Kansas County, Barber, ss.

**NOV 21 2007**

CONSERVATION DIVISION  
WICHITA, KS

Mark Morgenstern (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Mark Morgenstern  
 (Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 16 day of November, 20 07

Glenda Morrison My Commission Expires: 11/30/10  
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*[Handwritten signature]*