

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
**Type or Print on this Form  
Form must be Signed  
All blanks must be Filled**

Lease Operator: EOG Resources, Inc.  
 Address: 3817 N.W. Expressway ; Suite 500 Oklahoma City , OK 73112-1483  
 Phone: ( 405 ) 246 - 3100 Operator License #: 5278 *KCC PLS*  
 Type of Well: D & A Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: 10/26/2007 (Date)  
 by: Lynn Reimer (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
St. Louis Depth to Top: 6190' Bottom: 6194' T.D. 6350'  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 189-22548-0000  
 Lease Name: Mosbacher *KCC PLS CP 2113*  
 Well Number: # 1  
 Spot Location (QQQQ): NE - SE - NE - NW  
900 Feet from  North /  South Section Line  
2100 Feet from  East /  West Section Line  
 Sec. 11 Twp. 32 S. R. 38  East  West  
 County: Stevens  
 Date Well Completed: 11/16/2006  
 Plugging Commenced: 10/31/2007  
 Plugging Completed: 11/01/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
St Louis	Dry	Surface	1650'	8 5/8"	1650'	none
		Surface	6349'	4 1/2"	6349'	3983'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.  
POH w/ tbg & load csg w/ mud . Set 4 1/2" CIBP @ 6140' , cap w/ 2 sks cement . Load csg w/ mud . Cut & pull 4 1/2" casing from 3983' .  
Run tbg @ 3983' & spot 40 sks class "C" cement up to 3883' . Pull up hole w/ tbg @ 1750' & spot 100 sks class "C" cement up to 1450' . Pull up hole w/ tbg @ 475' & spot 40 sks cement up to 375' , POH w/ tbg & top out 40' - 4' w/ 12 sks cement .

Name of Plugging Contractor: Orr Enterprises, Inc. License #: 33338 **RECEIVED KANSAS CORPORATION COMMISSION**  
 Address: P. O. Box 1706 Duncan , OK 73534

Name of Party Responsible for Plugging Fees: EOG Resources Inc. **NOV 21 2007**  
 State of OK County, OK , ss. **CONSERVATION DIVISION WICHITA, KS**

Bev Christensen (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Bev Christensen  
 (Address) \_\_\_\_\_

SUBSCRIBED and SWORN TO before me this 19<sup>th</sup> day of November 2007  
Kaye Dawn Rockel My Commission Expires \_\_\_\_\_  
 Notary Public **NOTARY SEAL PUBLIC** **KAYE DAWN ROCKEL**  
 Notary Public State of Oklahoma  
 Commission # 04009575 Expires 10/21/08