

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: MIDCO Exploration, Inc.
Address: 414 Plaza Drive, Suite 204 Westmont, IL 60559
Phone: (630) 655 - 2198 Operator License #: 5254
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 11/7/07 (Date)
by: Steve Van Giesen - Wichita office (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 4123 Bottom: 4129 T.D. 4124
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 095-20444-00-01
Lease Name: Julia Tunney
Well Number: 1
Spot Location (QQQQ): C - SW - _____ - _____
1320 Feet from North / South Section Line
3950 Feet from East / West Section Line
Sec. 26 Twp. 28 S. R. 8 East West
County: Kingman
Date Well Completed: 2/14/76
Plugging Commenced: 11/14/07
Plugging Completed: 11/15/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Production	Csg	4 1/2"	4124'	none
		Surface	Csg	8 5/8"	268	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set cast iron bridge plug at 4060' ; perforate at 1175' ; squeeze with 50 sacks cement; lay tubing down; wait for cement to set up; trip back to 1138' ; pump 100 sacks cement to surface; come back next day and fill hole with 30 sacks cement.

Name of Plugging Contractor: Leiker Well Service License #: 30891

Address: P.O. Box 1902 Great Bend, KS 67530-1902

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: MIDCO Exploration, Inc.

DEC 11 2007

State of Illinois County, DuPage, ss.

CONSERVATION DIVISION

Earl J. Joyce, Jr. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) _____

(Address) 414 Plaza Drive, Suite 204 Westmont, IL 60559

SUBSCRIBED and SWORN TO before me this 7th day of December

Nancy L. Macyunas
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202