

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc.
Address: P. O. Box 783188
Phone: (316) 691-9500 Operator License #: 4767
Type of Well: ERW Docket #: E-23,601
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 11/27/2007 (Date)
by: Marvin Mills (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 4070' Bottom: 4080' T.D. 4200'
LKC Depth to Top: 4092' Bottom: 4102' T.D. 4200'
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 195-21381-0001
Lease Name: Schimkowitsch AP *Fig 2*
Well Number: 1 ERW *Per spot location*
Spot Location (QQQQ): NW - SW - SW - NE
2200 Feet from North / South Section Line
2200 Feet from East / West Section Line
Sec. 1 Twp. 12 S. R. 25 East West
County: Trego
Date Well Completed: 11/21/1983
Plugging Commenced: 11/14/2007
Plugging Completed: 11/27/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC	Water	4070'	4080'	8.625"	261'	-0-
LKC	Water	4092'	4102'	4.50"	4197'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing down to 2850'. Pumped 90 sx 60/40 Pozmix w/ 4% gel + 300 hulls. Pulled tubing up to 1950'.
Pumped 90 sx 60/40 Pozmix w/ 4% gel + 300 hulls. Pulled tubing out of hole. Loaded casing with 125 sx 60/40 Pozmix w/ 4% gel + 100 hulls.
Shut in at 200#. Plugging complete at 12:15 p.m. witnessed and approved by Marvin Mills with the KCC

Name of Plugging Contractor: Express Well Service + Supply Inc License #: 6426
Address: P. O. Box 31 Russell, KS 67665

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.
State of Kansas County, Sedgwick, ss.


Peter J. Fiorini - employee of Ritchie Exploration, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

(Address) P. O. Box 783188 Wichita, KS 67278-3188

SUBSCRIBED and SWORN TO before me this 7th day of December, 20 07

Debra K. Phillips My Commission Expires: 5-4-11
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*KCC PKT
Per CP 2/3*

**RECEIVED
DEC 10 2007**

KCC WICHITA

PM

ALLIED CEMENTING CO., INC. 28783

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
OAKLEY, KS

DATE 11-27-07	SEC. 1	TWP. 12S	RANGE 25W	CALLED OUT	ON LOCATION 7:15am	JOB START 12:00pm	JOB FINISH 12:30pm
Schimko wilsch LEASE		WELL# Ap-#1	LOCATION Wada Rd + I-70		COUNTY Trego	STATE KS	
OLD OR NEW (Circle one)			Hwy 40 2w-12N-12E in				

CONTRACTOR Express Well Service
 TYPE OF JOB AWP
 HOLE SIZE _____ T.D. _____
 CASING SIZE 4"2 DEPTH _____
 TUBING SIZE 2 3/8 DEPTH 2925'
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER same
 CEMENT
 AMOUNT ORDERED 375 60/40 40 gell
800# hulls
(used 305 + 700# hulls)

EQUIPMENT
 PUMP TRUCK CEMENTER Fuzzie
 # 422 HELPER Wayne
 BULK TRUCK
 # 399 DRIVER Lennie
 BULK TRUCK
 # 394 DRIVER Kelly

COMMON	<u>183</u>	@ <u>12.60</u>	<u>2305.80</u>
POZMIX	<u>122</u>	@ <u>6.50</u>	<u>780.80</u>
GEL	<u>10</u>	@ <u>16.50</u>	<u>166.80</u>
CHLORIDE		@	
ASC		@	
		@	
Hulls	<u>145k</u>	@ <u>25.50</u>	<u>357.00</u>
		@	
		@	
		@	
		@	
HANDLING	<u>404</u>	@ <u>1.90</u>	<u>767.60</u>
MILEAGE	<u>109.85</u>	@ <u>1.50</u>	<u>1647.75</u>
			TOTAL <u>6122.98</u>

REMARKS:

90SKS @ 2925' w/300#hulls
90SKS @ 1900' w/300#hulls
Pull all lbs. Hook ups wedge +
pump 125SKS w/100#hulls.
max pressure 400# shut in @ 200'
Job complete @ 12:15pm
Thanks Fuzzie crew

SERVICE

DEPTH OF JOB	<u>2925'</u>	
PUMP TRUCK CHARGE	<u>95.00</u>	
EXTRA FOOTAGE	@	
MILEAGE	<u>48</u>	@ <u>6.00</u> <u>288.00</u>
MANIFOLD	@	
	@	
	@	
TOTAL <u>1243.00</u>		

CHARGE TO: Ritchie Exploration
 STREET _____
 CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
TOTAL _____		

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Thomas A. [Signature]

PRINTED NAME [Signature]

RECEIVED
 DEC 11
 KCC WICHITA