

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 06 2007

CONSERVATION DIVISION
WICHITA, KS

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Lease Operator: EOG Resources, Inc.

Address: 3817 NW Expressway ; Suite 500 Oklahoma City , OK 73112

Phone: (405) 246 -3100 Operator License #: 5278

Type of Well: gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 11/20/2007 (Date)

by: Steve Durant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 175-22066-01-00

Lease Name: Lanora 1

Well Number: # 1H

Spot Location (QQQQ): E2 - NE - SE - NE
1650 Feet from North / South Section Line

175 Feet from East / West Section Line

Sec. 1 Twp. 34 S. R. 33 East West

County: Seward

Date Well Completed: 10/14/2006

Plugging Commenced: 11/21/2007

Plugging Completed: 11/29/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	1680'	9 5/8"	1680'	none
		Surface	6385'	7"	6385'	2316'
		Surface	7601'	4 1/2"	7601'	3915'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set 4 1/2" CIBP @ 5218' , cap w/ 2 sks cement . Load csg w/ mud . Cut & pull 4 1/2" csg from 3915' . TIH w/ tbg & spot 40 sks cement up to 3415'
Cut & pull 7" csg from 2316' . TIH w/ tbg @ 2300' & spot 50 sks cement up to 2170' , Pull up hole w/ tbg @ 1710' & spot
100 sks class "C" cement up to 1405' . Pull tbg up to 690' & spot 50 sks class "C" cement up to 540' . Pull out of hole w/ tbg & top out 40' - 4'
w/ 15 sks cement .

Name of Plugging Contractor: Orr Enterprises, Inc. License #: 33338

Address: P. O. Box 1706 Duncan, OK 73534

Name of Party Responsible for Plugging Fees: EOG Resources Inc KCC Pkt Per

State of OK County, OK, ss. Oper. Beau

Beu Christensen (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Beu

(Address) 3817 NW Exp Ste 500 OKC OK 73112

SUBSCRIBED and SWORN TO before me this 3rd day of December, 2007

Quiana J. Lehead 01010621 My Commission Expires: 6-30-09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202