

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Evans Oil, Inc

Address: PO Box 67 Lebo, KS 66856

Phone: (620) 437-2595 Operator License #: 6078

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 11-08-07 (Date)

by: Mike Heffern, District #3 (KCC District Agent's Name)

Is ACO-1 filed? Yes No NA If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Mississippi Depth to Top: 1799' Bottom: 1804' T.D. 1831'

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15-073-22421-00-00

Lease Name: Harschman Farms Twin

Well Number: 6 Harschman Farm Twin

Spot Location (QQQQ): - NE - SW - SE 990 Feet from North / South Section Line

1650 Feet from East / West Section Line

Sec. 8 Twp. 23 S. R. 13 East West

County: Greenwood

Date Well Completed: 9/82

Plugging Commenced: 11-08-07

Plugging Completed: 11-08-07

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows show casing sizes of 8 5/8" and 4 1/2" with depths of 150' and 1831' respectively.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Spot plugs down 2 3/8" tubing as follows: 200# gel spacer, 20sxs @ 1700', Perforate 2 shots @ 800', 100# gel spacer, 25sxs @ 800', Perforate 2 shots @ 165', 75sxs @ 165' to surface

RECEIVED KANSAS CORPORATION COM

DEC 06 2007

Name of Plugging Contractor: Schankie Well Service, Inc. License #: 6470

Address: 1006 SW Blvd, PO Box 397 Madison, KS 66860

CONSERVATION DIVISION WICHITA, KS

Name of Party Responsible for Plugging Fees: Evans Oil, Inc. PO Box 67 Lebo, KS 66856

State of Kansas County, Greenwood, ss.

Randall Schankie (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) PO Box 397 Madison, KS 66860

SUBSCRIBED and SWORN TO before me this 20th day of November, 2007

Carol R. Bolen My Commission Expires: 1/9/2009 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



KCC PKT P01 CP2/3

[Handwritten initials]