

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: BLACK DIAMOND OIL, INC.
Address: P.O. Box 641 Hays, KS 67601
Phone: (785) 625 5891 Operator License #: 7076
Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 10/3/07 (Date)
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
None Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 065-23,349-0000
Lease Name: STEHNO
Well Number: 2
Spot Location (QQQQ): C - S/2 - SW - NE
2250 Feet from North / South Section Line
1960 Feet from East / West Section Line
Sec. 25 Twp. 7 S. R. 22W East West
County: Graham
Date Well Completed: 10/3/07
Plugging Commenced: 5:15PM 10/3/07
Plugging Completed: 7:00PM 10/3/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	223	8 5/8	223	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug @ 1800'W/25sks 15sks In Rat Hole Circulated 1st Plug 15 Minutes W/58Vis Mud.
2nd Plug @ 1025'W/100sks 10sks In Mouse Hole Plugs displaced with mud
3rd Plug @ 275'W/40sks Total 200sks 60/40Poz 4%Gel W/1#CF/sk By Allied Cementing
4th Plug @ 40'W/10sks Completed @ 7:00PM 10/3/07

Name of Plugging Contractor: Discovery Drilling Co., Inc. License #: 31548
Address: P.O. Box 763 Hays, KS 67601
Name of Party Responsible for Plugging Fees: BLACK DIAMOND OIL, INC.
State of Kansas County, Ellis, ss.

Kenneth Vehige (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature)


(Address) P O Box 641

SUBSCRIBED and SWORN TO before me this 1st day of November, 2007

Melissa L. Windholz
Notary Public

My Commission Expires: 5/21/2011

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



RECEIVED
KANSAS CORPORATION COMMISSION
NOV 21 2007
CONSERVATION DIVISION
WICHITA, KS

PKT