

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-163-00522-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Rooks County, Sec. 26 Twp. 10S Rge. 20 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW  
Lease Owner Brooks Hall  
Lease Name Annon Well No. 1  
Office Address Box 1499 Oklahoma City, Okla.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-26 19 53  
Application for plugging filed 5-25 19 53  
Application for plugging approved 5-25 19 53  
Plugging commenced 5-25 12:00 19 53  
Plugging completed 5-26 4:30 A. M. 19 53  
Reason for abandonment of well or producing formation Dry Hole

NORTH

Annon # 1	
SW SW NW Sec 26	
Twp 10S Rge 20W	
Rooks County, Kansas.	

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Verbal

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3800 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Blue Shale		0	128	8 5/8	128'	None
Shale & Shells		400	1620			
Anhydrite		1620	1660			
Lime & Shale		2000	3402			
Lime		3402	3720			
Cherty Cong.		3720	3800			
T. D.		3800				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Stirred Pits well filled hole with heavy muc. Set wood plug @ 155' Ran 1/2 sack hulls and 15 sacks of cement. Filled hole with heavy mud to 40'. Set wood plug and ran 1/2 sack hulls and 10 sacks of cement. Filling hole to bottom of the cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strain Drilling Company  
Address Box 188 Hays, Kansas.

STATE OF Kansas. COUNTY OF Ellis, ss.  
T. C. Strain (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. C. Strain  
Box 188 Hays, Kansas.  
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of May, 19 53

My commission expires March 26, 1956

Mildred Schneider  
STATE CLERK Notary Public.

24-2675-5 2-52-20M

**PLUGGING**  
FILE SEC 26 T 10 R 20W  
BOOK PAGE 104 LINE 18

JUN 1 1953  
06-02-1953  
CONSERVATION DIVISION  
Wichita, Kansas

15-163-00522-00-00

WELL LOG

COMPANY: Brooks Hall

SW SW NW Sec 26  
Twp 10S Rge 20W  
Rooks County, Kansas.

LEASE: Annon # 1

ELEVATION: 2178 R. B.

NOTE: All meas Rotary Bushing

0	40 Soil & Postrock
40	126 Blue Shale
126	400 Blue Shale
400	810 Shale & Shells
810	900 Sand & Shale
900	985 Shale & Shells
985	1150 Shale & Shells
1150	1270 Shale & Sand
1270	1320 Sand (Hard)
1320	1400 Sahn, Shells & Redbed
1400	1620 Sahel & Redbeds
1620	1660 Anhydrite
1660	1800 Shale & Shells
1800	2000 Shale & Shells
2000	2135 Lime & Shale
2135	2245 Lime & Shale
2245	2280 Lime & Shale
2280	2310 Lime
2310	3400 Lime & Shale
2400	2540 Lime & Shale
2540	2610 Lime & Shale
2610	2810 Lime & Shale
2810	2935 Shale & Lime
2935	3025 Shale & Lime
3025	3110 Shale & Lime
3110	3270 Broken Line
3270	3360 Lime & Shale
3360	3402 Lime
3402	3460 Lime
3460	3510 Lime
3510	3550 Lime
3550	3590 Lime
3590	3630 Lime
3630	3680 Lime
3680	3720 Lime

3720	3748 Cherty Cong.
3748	3775 Cherty Cong.
3775	3800 Conglomerate
3800	( Total Depth)

COMMENCED: 5-15-53  
COMPLETED: 5-26-53

CASING RECORD:

8 5/8 Surface Casing set 128' w/90 sacks of cement by Globe Cementing Co.

Schlumberger Logs Run

Geologist: Donald Dodge.

TOPS

Geological

Anhydrite	1620 (+558)	Lansing K. C.	3456 (-1278)
Heebner	3416 (-1238)	Conglomerate	3722 (-1544)
Toronto	3438 (-1260)	Arbuckle	3789 (-1611)
		T. Depth	3800 (-1622)

STATE OF KANSAS) SS  
COUNTY OF FULTON)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Annon # 1, located SW SW NE, Sec 26, Twp 10S, Rge 20W, Rooks County, Kansas.

CONTRACTOR: Strain Drilling Company

By: T. C. Strain  
T. C. Strain

Subscribed and sworn to before me this 29th day of May 1953  
My commission expires March 26, 1956

06-02-1953

Mildred Schneider  
Notary Public

PLUGGING

TRK SEC 26 T 10 R 20W

DESK PAGE 104 LINE 18