

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

RECEIVED
10-24-2003
OCT 24 2003

KCC WICHITA

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Bowman Oil Company
Address: 805 Codell Road, Codell, KS 67663
Phone: (785) 434 - 2286 Operator License #: 6931

Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: Oct 9, 2003 (Date)

by: Dennis Hamel (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3763 Bottom: 3768 T.D. 3773

API Number: 15 - 163-03432-00-00

Lease Name: Sutor "C"

Well Number: 1

Spot Location (QQQQ): NW - SW - SE

990 Feet from North / South Section Line

2310 Feet from East / West Section Line

Sec. 26 Twp. 10 S. R. 20 East West

County: Rooks

Date Well Completed: Sept 22, 1957

Plugging Commenced: Oct 9, 2003

Plugging Completed: Oct 9, 2003

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	oil & water	3763	3768	8 5/8	240	none
				5 1/2	3768	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

5 1/2 - mixed 25 sx w/ 3 hulls, 20 get and 150 sx w/ 1 hull; press to 1000 psi. Shut in @ 300 psi.

Annulus - 25 sx w/ 1 hull press to 500 psi. Shut in @ 400 psi

Name of Plugging Contractor: Allied Cementing Co Inc License #: _____

Address: PO Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: Louis D Bowman for Bowman Oil Company

State of Kansas County, Rooks, ss.


Louis D Bowman (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Louis D. Bowman

(Address) 805 Codell Road, Codell, KS 67663

SUBSCRIBED and SWORN TO before me this 22nd day of October, 2003

Jackie J. Langholz My Commission Expires: 2-24-2005
Notary Public



RECEIVED
 SEP 29 2003
 09-29-2003
 KCC WICHITA

15-163-03432-00-00 *Section C #1*

El Dorado Refining Co. - Owner

Sierra Petroleum - Contr.

SUROR #1

NW SW SE Sec. 26-106-20W
 Rooks County, Kansas

Total Depth: 3773'

Elev: 2217 MB

Comm: 9/11/57
 Comp: 9/22/57

Casings:

Cement:

3 5/8" @ 240'
 3 1/2" @ 3763

with 150 sacks cement
 with 150 sacks cement

FORMATION	DEPTH	SAMPLE TOPS
Sand rock	40	Heeb. 3437
Shale & sand	125	Tor. 3463
Shale & shells	780	Lan. 3476
Sand, shale	990	BKC 3688
Shale & shells	1120	Cong. 3718
Shale & sand	1335	Simp. 3752
Red bed	1645	Arb. 3766
Anhydrite	1680	RTD 3773
Shale & shells	1690	
Shale, shells & salt	1950	
Shale & salt	2120	
Shale & lime	3467	
Lime	3761	
Dolomite	3773	

Top: Arbuckle 3766

STATE OF KANSAS)
) ss:
 COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct
 to the best of my knowledge.

C. P. Honsaker

Subscribed and sworn to before me this 23rd day of September, 1957.

Margie Cooper
 Notary Public

My commission expires: 1-30-61.