

STATE OF KANSAS  
STATE CORPORATION COMMISSION


15-163-03489-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Rooks County. Sec. 26 Twp. 10S Rge. (E) 20 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C SE NE NE  
Lease Owner Gulf Oil Corporation  
Lease Name Eliza Well No. 2  
Office Address P. O. Box 661, Tulsa, 2, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 3, 19 50  
Application for plugging filed May 15, (Verbally) 19 52  
Application for plugging approved May 15, (Verbally) 19 52  
Plugging commenced May 16, 19 52  
Plugging completed May 21, 19 52  
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production None 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty  
Producing formation Arbuckle Depth to top 3828' Bottom Total Depth of Well 3860 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8" OD	1593'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mixed and pumped (at 350 pounds pressure) 60 sacks of cement into 8-5/8" OD casing with bottom plug ahead and filled cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 27 1952  
05-27-1952  
CONSERVATION DIVISION  
Wichita, Kansas

Cemented by Halliburton Oil Well Cementing Company  
Cellar filled by contract labor crew.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor None  
Address \_\_\_\_\_

STATE OF Kansas, COUNTY OF Rice, ss.  
H. H. Wright (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H. H. Wright*

P. O. Box 544, Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of May, 1952

My commission expires April 14, 1956 *AMC* Notary Public.

23-8390-s 6-51-20M  
PLUGGING  
FILE SEC 26 T 10 R 200  
BOOK PAGE 18 LINE 35

**WELL RECORD**  
GULF 880-A

15-163-03489-00-00

WELL NO. 2 LEASE Eliza COMPANY Gulf Oil Corporation A.F.E. 2287

DATE—DRILLING BEGAN 4-22-50 WELL COMPLETED 5-3-50 FIRST PRODUCTION — —

SAND RECORD Top Arbuckle 3828' TOTAL DEPTH 3860'

INITIAL PRODUCTION Dry Hole. Will hold for possible use as SWD well.

**CASING RECORD**

SIZE	WEIGHT	THD.	CLASS	MAKE	SET AT DEPTH	SACKS CEMENT	LBS. CAL. CHLO.	PULLED	LEFT IN
8-5/8"	24	8R	A	Smls.	1593'	600			1593'

S-26 T-10S R-20W

C-					
SE					0
NE					
NE					
Rocks					
County					
Kansas					

ELEVATION— 2155'

DISTANCE H: Top collar is 9' below rotary bushing.

**FORMATION RECORD:**

	From	To
Shale & shells	0'	1100'
Sand		1320
Shale & shells		1520
Shale, chalk & anhydrite		1593
Anhydrite		1595
Shale & shells		1950
Shale & lime		2140
Lime & shale		2560
Shale & lime		2740
Lime & shale		3290
Lime		3365
Lime & shale		3450
Lime		3680
Lime & chert		3735
Chert & conglomerate		3765
Lime & chert		3860

TOTAL DEPTH

ED:RL

5-26-50

**RECEIVED**  
STATE CORPORATION COMMISSION

**PLUGGING** CONSERVATION DIVISION  
FILE SEC 26 10 20  
PAGE 12 LINE 35

MAY 29 1952  
05-29-1952  
Wichita, Kansas