

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-163-00371-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

ROOKS

County. Sec. 26 Twp 10 Rge. 20 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE/4 NE/4 SE/4

Lease Owner NADEL AND GUSSMAN

Lease Name Nadel and Gussman-Sutor Well No. 1

Office Address Union National Bank Bldg., Wichita, Kans.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed December 31 1949

Application for plugging filed September 7 1954

Application for plugging approved September 8 1954

Plugging commenced September 27 1954

Plugging completed October 2 1954

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production August 1954

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Arbuckle Depth to top 3728 Bottom 3733 Total Depth of Well 3733 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	167'	None
				5 1/2"	3729'	1998'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3733 feet to Surface feet for each plug set.

Hole filled with sand from 3733 to 3660; five sacks of cement placed in hole with dump bailer to form cement plug from 3660 to 3620; Twenty Sacks of mud and plug pumped down, and fifty sacks of cement pumped in hole with Halliburton cementing pumps.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes and Sons Pine Pulling Co

Address Russell, Kansas.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

Herbert Gussman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Herbert Gussman*


Drawer 309, Tulsa 1, Oklahoma.
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of October, 1954

My commission expires April 1, 1957

Jack Brown
Notary Public.

24-2675-S 2-52-20M



10-13-1954

15-163-00371-00-00

WELL LOG

NADEL AND GUSSMAN

SUTOR No. 1

NE SE 26-10-20W
ROOKS COUNTY, KANSAS

COMM. 12-14-49W
COMP. 12-31-49

Casing:
167' 8-5/8" - 85 sax
3729' 5-1/2" - 125 sax

<u>Formation</u>	<u>Depth</u>
Sand and Shale	145
Shells and shale	167
Shale and shells	1090
Sand	1305
Shale and shells	1335
Shale and sand	1400
Shale and Red Rock	1575
Anhydrite	1615
Shale and shells	2210
Shale and Lime	2655
Broken lime	2750
Shale and lime	2940
Shale 2990	2990
Shale and lime	3080
Shale and shells	3163
Shale and lime	3175
Lime	3355
Shale and lime	3395
Shale	3409
Shale and lime	3424
Lime	3623
Lime and shale	3665
Conglomerate	3700
Shale	3728
Arbuckle Lime	3733

GEOLOGICAL TOPS

Topeka	3174
Heebner	3386
Lansing-Kansas C.	3425
Conglomerate	3667
Simpson Shale	3721
Arbuckle	3728

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS:

L. C. Hay, of lawful age, being first duly sworn on his oath, states that the above formations and depths are true and correct according to daily drilling log of the Sutor No. 1 Well in the NE SE of Section 26-10S-20W, Rooks County, Kansas.

PLUGGING

FILE SEC. 26-10-20W
BOOK PAGE 62 LINE 17

L. C. Hay

Subscribed and sworn to before me this 4th day of January, 1950.

09-08-1954

Paul B...
Notary Public

My commission expires Nov. 3, 1952