


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rooks County, Sec. 26 Twp. 10 Rge. 20 (E) (W)  
Location as "NE/CNW/SW" or footage from lines SWNWSE 1/4  
Lease Owner Herman Geo. Kaiser, Oil Producer  
Lease Name Sutor Well No. 1  
Office Address 909 Palace Bldg., Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed Oct. 24, 19 57  
Application for plugging filed Oct. 24, 19 57  
Application for plugging approved Oct. 24, 19 57  
Plugging commenced Oct. 24, 19 57  
Plugging completed Oct. 24, 19 57  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3824 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	201	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole with heavy rotary mud to 650 ft., set plug and cemented with 20 sacks cement through drill pipe. Mudded hole with heavy mud to 190 ft., set plug and 20 sacks cement through drill pipe. Mudded hole to 40 ft. set plug and cemented with 10 sacks cement and 1/2 sack Hulls to bottom of cellar.

11-09-1957

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor H-30, Inc.  
Address 709 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. employee of contractor  
L. C. Sponenberg (employee of owner) of (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. C. Sponenberg*  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of November, 19 57

My commission expires Feb. 13, 1960

*Rose Turey*  
Notary Public.

PLUGGING  
SEC 26 T 10 R 20 W  
BOOK PAGE 56 LINE 36

15-163-03098-00-00

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Herman Geo. Kaiser, Oil Producer**

SEC. 26 T. 10 R. 20

FARM **Auton** NO. **1**


LOC. SW NW SE 1/4

TOTAL DEPTH **3821'**  
COMM. **10-21-57** COMP. **10-21-57**

COUNTY **COOKS**

KANSAS

SHOT OR TREATED  
CONTRACTOR  
ISSUED



CASING  
20 10  
15 8 **201'**  
12 6  
13 5

2224 F.S.  
ELEVATION 2221 F.S.  
2219 F.S.  
PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

Top Soil	10
Sand	50
Shale	201
(cont)	
Shale	670
Shale - sand streaks	1170
bank	1304
Shale - Shells	1557
Anhydrite	1696
Shale - Shells	2150
Shale / fine streaks	2195
Line - shale	2280
Shale - Shells	2820
Shale - Sand	3198
Line - Shert	3430
Line	3638
Line - Shale	3693
Line - Sand	3708
Line - Shale	3738
Shale - Shert	3797
Dimpson	3805
Aruckle	3821

FORMATION FEET:

Nechner	3455
Topokv	3475
F.C.	3495
Conglomerate	3713
Aruckle	3805

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

11-30, 1957.

*L. C. Zponenberg*  
L. C. Zponenberg

STATE OF KANSAS )  
                          )  
COUNTY OF STEPHENSON )

Subscribed and sworn to before me, a notary public, in and for said County and State this 5th day of November, 1957.

*Notary Public*

My Commission expires February 13, 1960.

PLUGGING  
SEC 26 T. 10 R. 20  
BOOK PAGE 56 LINE 36

11-09-1957