

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

15-163-02195-00-00
WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 5-10-57

LEASE NAME ARMBRISTER "B"

WELL NUMBER 1

330 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 26 TWP. 10S RGE. 20 (XXXX W)

COUNTY Rooks

Date Well Completed 5-10-57

Plugging Commenced 9-5-85

Plugging Completed 9-6-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR FINA OIL & CHEMICAL COMPANY

ADDRESS 1601 N.W. Expressway, Ste. 900
Oklahoma City, OK 73118

PHONE#(405) 840-0671 OPERATORS LICENSE NO. 5692

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3732' Bottom _____ T.D. 3746'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	225'	-0-
				5-1/2"	3733'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

RU Cementer and pumped cement plugs down tubing as follows: 100 sx 60/40 pozmix w/10% gel at 2990', max. pressure 700 psi, 100 sx at 1800', 700 psi, 1 sx hulls and 65 sx at 794', circulate to top, pulled tubing, tied onto 5-1/2" and pumped 1 sx hulls and 35 sx cement, 1500 psi, witnessed by Dennis Hamel w/KCC.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cement License No. NA

Address 332 W. Wichita, Russell, KS 67665

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

DAVID A. RIDDY (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David A. Riddy
1601 N.W. Expressway, Ste. 900
(Address) Oklahoma City, OK 73118

SUBSCRIBED AND SWORN TO before me this 16th day of October, 19 85

My Commission Expires: 7/6/88 Raylene M. Smith Notary Public

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1985
10-21-1985
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 08-84