


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

15-163-00947-00-00 Form CP-4

NORTH



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 26 Twp. 10 Rge. 20 (E) _____ (W) _____
Location as "NE/CNW/SW" or footage from lines W/2 NE
Lease Owner Austin Construction Company
Lease Name Eliza Well No. 1
Office Address Stafford, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1/8/69 _____ 19____
Plugging completed 1/9/69 _____ 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3788 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	270	none
				5 1/2"	3780	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3788' and ran sand to 3770'. Dumped 5 sacks of cement.
Mudded to 650' and set 20' rock bridge. Ran 4 yards ready mix from 650
to top of hole.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JAN 16 1969
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor _____
Address _____
(If additional description is necessary, use BACK of this sheet)
KNIGHT CASING PULLING CO., INC.
Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss.
Noel J. Knight

well, being subscribed and sworn to on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 10th day of January, 19 69

My commission expires February 15, 1971

Notary Public.

15-163-00947-00-00

Kaiser-Francis
Ellinwood, Dist
Ellinwood, Kansas

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1968
CONSERVATION DIVISION
Wichita, Kansas

Well records And Logs

Eliza #1
NW-NW-NE
26-10-20
Rocks Co
Commenced-10-31-55
Completed-11-11-55
Contractors-Armer Drlg Co

Elevation 2203 R.B.
8 5/8 O.D. Casing set at
200' W/135 sacks
5 1/2 O.D. Casing set at
3788' W/150 sacks
Centralizers set at
3780-3736-3701-3677

Summary Of Formations

Reebner-----3434(-1231)
Toronto-----3458(-1255)
Lansing-----3472(-1269)
Base Of K.C.-----3686(-1483)
Cherty Conglomerate-----3716(-1513)
Simpson-----3761(-1558)
Arbuckle-----3786(-1583)
Notary T.D.-----3796(-1593)

Drill Stem Tests

1. 3495-3545' Open 1 Hr, Recovered 90' Muddy Water. IFP 0%. FFP 75%.
BHSIP 1160#.
2. 3621-3682' Open 1 Hr, Recovered 12' Mud BHP 0%.
3. 3787-3791' Open 1 Hr, Recovered 50' of heavy black oil. BHSIP 390#.
4. 3790-3796' Open 1 Hr, Recovered 1010' Oil. IFP 300%. BHSIP 975# in 15".

Cable Tools

Nov 14-55 R.J. Swab-C.O.-To Float
Nov 15-55-Drlg Cement-Drlg Shoe @ 3788', C.O. To Ret T.D. or 3796'
-Fill up-2400'-6 Hr No Water-Swab 12 BBL OIL Per Hr
1700' off Bottom-(24 Gty)
Nov 16-55-Tear Down-To Put on Pump.

Temporary Productivity Filed November 15, 1955

WJH/dp

Kaiser-Francis

W. J. Hall
W. J. Hall

KANSAS GEOLOGICAL SOCIETY
KANSAS L LOG BUREAU - KANSAS WELL SAM E BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Kaiser-Francis

15-163-00947-00-00

SEC. 26 T. 10S R. 20W

FARM Klisa

NO. 1

LOC. NW NW NE

TOTAL DEPTH 3796'

COMM. 10/31/55

COMP. 11/11/55


COUNTY Rocks

KANSAS

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED



CASING

20 10
15 8 200'
12 6
13 5 3788'

ELEVATION 2203 R.B.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	702
Sand	731
Shale with Sand Streaks	800
Shale & Sand	970
Shale	1125
Sand	1340
Shale & Shells	1585
Shale, Shells & Red Bed	1660
Anhydrite	1695
Shale, Shells & Red Bed	1943
Shale, Shells & Salt	2225
Shale & Lime Shells	2355
Shale & Lime	3728
Lime, Shale & Chert	3767
Cherty Lime	3767
Lime	3791
Lime & Chert	3796

FORMATION TOPS

LANSING	3472
B SE KANSAS CITY	3686
CONGLOMERATE	3716
ARBUCKLE	3786

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By [Signature]

STATE OF KANSAS

SS:

COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 15th day of November, 1955.

[Signature]
Notary Public

My Commission expires February 13, 1956.

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1968
CONSERVATION DIVISION
Wichita, Kansas