

STATE OF KANSAS
STATE CORPORATION COMMISSION
300 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-01649-00-00
API NUMBER drilled 5/52

LEASE NAME Bassett

WELL NUMBER 1

330 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 1 TWP. 10 RGE. 21 (E) or (W)

COUNTY Graham

Date Well Completed 5/25/52

Plugging Commenced 1:00P.M. 2/18/88

Plugging Completed 2:00P.M. 2/18/88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE#(913) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 18, 1988 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3836 Bottom 3841 T.D. 3841

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	147.71'	None
				5 1/2"	3840.59'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Down 5 1/2" csg., at 1000# max. pressure, mixed 25 sx cement then mixed 5 sx hulls with 150 sx cement and shut in at 700#.
Pressured annulus to 1000# and shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address Box 31, Russell, Kansas 67665

STATE OF KANSAS COUNTY OF Phillips, ss.

Harold Parsons (Employee of Operator) or (XXXXXX) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Harold Parsons

(Address) Box 353, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 29 day of February, 19 88



My Commission Expires: July 17, 1988 Notary Public Betty Jane Bittel

03-04-1988
Form CP-4
Revised 07-87

CONTRACTOR'S WELL LOG

OPERATOR D. G. HANSEN FARM NAME BASSETT #1
 LOCATION SW SW SW Sec. 1-10-21W
 POOL NAME _____ COUNTY Graham STATE Kansas
 COMMENCEMENT DATE May 15, 1952 COMPLETION DATE May 25, 1952

LOG OF WELL

Elevation: 2284 R. B.
 All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	148			
148	915	Shale-Sand-Shells		
915	1260	Shale		
1260	1470	Sand		
1470	1750	Shale	0° - 1500'	
1750	1760	Anhydrite		
1760	1790	Anhydrite		
1790	2000	Shale	0° - 2000'	
2000	2240	Lime-Shale		
2240	2350	Lime-Shale		
2350	2450	Lime-Shale		
2450	2565	Lime-Shale	0° - 2500'	
2565	2650	Lime-Shale		
2650	2780	Shale-Lime		
2780	2880	Lime-Shale		
2880	2950	Lime-Shale		
2950	3015	Lime-Shale	0° - 3000'	
3015	3110	Lime-Shale		
3110	3210	Lime-Shale		
3210	3310	Lime-Shale		
3310	3385	Lime-Shale		
3385	3440	Lime		
3440	3505	Lime	0° - 3500'	
3505	3550	Lime		
3550	3600	Lime		
3600	3645	Lime		
3645	3680	Lime		
3690	3740	Lime		
3740	3790	Lime		
3790	3837	Lime-Shale		
3837	3839	Lime		

CASING LEFT IN HOLE AFTER COMPLETION

Ran 147.71' (5 jts) of 8 5/8" Casing.
 Ran 3840.59' (122 jts) of 5 1/2" Casing.

04-04-1988

STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By *Wick L...*

Subscribed and sworn to before me this 28th day of May, 1952.

My commission expires:

November 21, 1955

Maryann Schmidt
 Notary Public

15-065-01649-00-00

CONTRACTOR'S WELL LOG

OPERATOR D. G. HANSEN FARM NAME BASSETT #1

LOCATION SW SW SW Sec. 1-10-21W

POOL NAME _____ COUNTY Graham STATE Kansas

COMMENCEMENT DATE May 15, 1952 COMPLETION DATE May 25, 1952

LOG OF WELL

Elevation: 2284 R. B.
All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	148			
148	915	Shale-Sand-Shells		
915	1260	Shale		
1260	1470	Sand		
1470	1750	Shale	0° - 1500'	
1750	1760	Anhydrite		
1760	1790	Anhydrite		
1790	2000	Shale	0° - 2000'	
2000	2240	Lime-Shale		
2240	2350	Lime-Shale		
2350	2450	Lime-Shale		
2450	2565	Lime-Shale	0° - 2500'	
2565	2650	Lime-Shale		
2650	2780	Shale-Lime		
2780	2880	Lime-Shale		
2880	2950	Lime-Shale		
2950	3015	Lime-Shale	0° - 3000'	
3015	3110	Lime-Shale		
3110	3210	Lime-Shale		
3210	3310	Lime-Shale		
3310	3385	Lime-Shale		
3385	3440	Lime		
3440	3505	Lime	0° - 3500'	
3505	3550	Lime		
3550	3600	Lime		
3600	3645	Lime		
3645	3680	Lime		
3680	3740	Lime		
3740	3790	Lime		
3790	3837	Lime-Shale		
3837	3839	Lime		

STATE OF KANSAS

REC 9 1957
12-09-1987
Notary Public
Wichita, Kansas

RECEIVED
MAY 10 1952

D. G. Hansen, Contractor
By _____

CASING LEFT IN HOLE AFTER COMPLETION

Ran 147.71' (5 jts) of 8 5/8" Casing.
Ran 3840.59' (122 jts) of 5 1/2" Casing.

STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By *[Signature]*

Subscribed and sworn to before me this 28th day of May, 1952.

My commission expires:
November 21, 1955

Marilyn Schmidt
Notary Public