

15-065-01650-00-00 137
2-18-88 R

6 031041

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1952
SW SE SW, SEC. 1, T 10 S, R 21 WYE
330 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5258
Operator: D. G. Hansen Trust
Name & Address: Box 187
Logan, Ks. 67646

Lease Name Bassett Well # 2
County Graham 124-80
Well Total Depth 3840 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 158

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number
Address Plainville, Ks.

Company to plug at: Hour: PM Day: 18 Month: Feb Year: 19 88

Plugging proposal received from Johnnie Parsons
(company name) Hansen Trust (phone)

were: 8 5/8" set at 158' w/125 sks cwc. 5 1/2" set at 3829' w/100 sks. Squeezed at 1450' w/300 sks. Perf at 3595' - 3615'. Order 200 sks ATL Cement Blend 65/35 Poz 10%, Gel 2% Dical 5 sks Hulls. Allied Cement Co. OWS Water Truck and company truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:00 PM Day: 18 Month: Feb Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 5 1/2" w/175 sks Cement Blend w/4 sks Hulls mixed in to Max Psi 750#. Close in Psi 300#. Squeeze 8 5/8" - 5 1/2" Annulus w/50 sks Cement Blend w/1 sk Hulls mixed in to Max Psi 300#. Close in 200#. Plug completed.

STATE CORPORATION COMMISSION

04-22-1988
APR 22 1988

Remarks: (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
did not observe this plugging.

DATE 4-26-88
INV. NO. 20450

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow