

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22511-00-00
Spot: NENESW Sec/Twnshp/Rge: 25-13S-22W
2310 feet from S Section Line, 2310 feet from W Section Line
Lease Name: LARRY PEARSON Well #: 1-25
County: TREGO Total Vertical Depth: 4185 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	224		

136-01

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/23/2007 4:30 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 11/23/2007 6:30 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 1800' w/25 sxs.
2nd. Plug at 950' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED


DATE 12-14-07
INV. NO. 2008060903

RECEIVED
DEC 05 2007
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed 
(TECHNICIAN)

DEC 03 2007

PKT