

2-7

To: 6 031330
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,540-00-00

SE SW SW, SEC. 1, T 10 S, R 21 WAB

330 feet from S section line

4920 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3007

Lease Name Virginia Miller Well # 1

Operator: Western Ks. Exp
Name & Address: Box 126

County Graham 125.87

Well Total Depth 3873 feet

Conductor Pipe: Size feet

Surface Casing: Size 3 1/2" feet 260

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Western Ks. Drilling License Number 4083

Address Hays, Ks.

Company to plug at: Hour: PM Day: 7 Month: Feb Year: 19 90

Plugging proposal received from Stan Younger

(company name) W.K.E. (phone)

were: 8 5/8" set at 200' cwc. Rig moved off and hole was to be completed as SWD

later by Trogden but deal failed so WKE moved in. Express WUll Service to run 2 7/8

tubing to anhydrite and plug as D and A. Order 190 sks 60/40 poz 6% gel

3% CA1 CL. Halliburotn Cement Co. OWS Water Truck. Had to wash through heavy mud and cuttings about 1100'.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:00PM Day: 7 Month: Feb Year: 19 90

ACTUAL PLUGGING REPORT Run tubing to 1741' condition hole with mud. Spot 25 sks cement blend at 1741'.

Maintain mud at surface, w/good circulation, spot cement blend at 975' w/100 sks and hulls. Lay down pipe to 250' and displace w/40 sks cement blend and

hulls. Lay down tubing and adjust mud:top at 40' fill up 8 5/8" w/10 sks cement blend

to surface. Run a joint of tubing in rathole. Circulate to plow depth with 15 sks cement

blend. Elev. 2273 Anhy 1741. Good circ w/heavy mud all the way.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICE DIVE
DATE 2-26-90
INV. NO. 275-79
2-7

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow

APR 17 1990