

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-22534-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 29-30S-7E
4217 feet from S Section Line, 1842 feet from E Section Line
Lease Name: MELVIN STOLP Well #: 10
County: COWLEY Total Vertical Depth: 2930 feet

Operator License No.: 9576
Op Name: WHITEMAN, RON DBA GEN-DOR OIL C
Address: 8135 281ST RD
CAMBRIDGE, KS 67023

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2928		
SURF	8.625	210		

95.23

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/04/2007 8:00 AM
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.
Proposal Rcvd. from: RONNIE WHITEMAN Company: GEN-DOR OIL CO. Phone: (620) 467-2615

Proposed Plugging Method: FILL BOTTOM OF HOLE W/SAND TO 50' ABOVE PERFS DUMP BAIL 6 SXS CEMENT ON TOP. PULL PIPE, CIRC TO SURFACE FROM 350'. RIH W/TBG TAG BOTTOM PLUG, PRODUCTION CASING HAS ALREADY BEEN PULLED.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 12/07/2007 3:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

12-4-2007, RIH W/TBG TO TAG BOTTOM PLUG. TBG STACKED OUT @ 378'. 12-5-2007, CIRCULATED HOLE CLEAN FROM 378' TO 510'. 12-6-2007, CIRCULATED HOLE CLEAN FROM 510' TO 1509', TAGGED SOLID, COULD NOT GET BACK INTO CUT CSG. 12-7-2007, W/TBG @1505', GEN-DOR MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL, FLUIDS CIRCULATED @ SURFACE DURING CEMENT JOB. PULLED TBG @ 350', GEN-DOR OIL CO. MIXED & PUMPED 110 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 1530 PM 12-7-2007. UNITED CEMENTING TICKET #8072. 1509' OF 4-1/2" CSG WAS PULLED FROM THIS WELL.

Perfs:

INVOICED
DATE 12/20/07
INV. NO. 2008060952

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 17 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: -096.68256,37.41481, PERFS 2897'-2904'

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

PKG