

10-22

4-031779

15-065-01708-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 1959

NW SW SE /4 SEC. 08, 10 S, 21 W  
990 feet from S section line  
2310 feet from E section line

Operator license# 5285

Lease Wheeler well # 2

Operator: The Dane G. Hansen Trust

County Graham

Address: P.O. Box 187  
Logan, Kansas 67646

Well total depth 3802 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 181 feet

123.57

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling License# 6050

Address: Chase, Kansas

Company to plug at: Hour: P.M. Day: 22 Month: October Year: 92

Plugging proposal received from: Manny

Company: Kelso Casing Pulling Phone: \_\_\_\_\_

Were: Order 250 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
Hole open to perf.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 2:00P.M., Day: 22, Month: October, Year: 92

Actual plugging report: 8 5/8 set @ 181' w/150 sx. cwc. 5 1/2" set @ 3801' w/175 sx. P.B.T.D. 3708'. Perf. 3584' - 3699'. Shot @ 2200' and 1300'. Pumped bottom cement plug to perf. Laid down casing to 500' circ. cement to surface. Laid down casing. Squeezed 8 5/8" with total 225 sx. cement blend with 500# hulls mixed in - circulated cement into cellar. Plug complete.

NOV 9 1992  
11-09-1992  
Wichita, Kansas

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD  BAD  Any plug: YES  NO   
Bottom plug(in place): YES  , CALC  , NO  Dakota plug: YES  , NO   
Plugged through TUBING \_\_\_\_\_ , CASING  . Elevation: 2255 GL

I did  / did not  observe the plugging.

Carl Goodrow

DATE 11-18-92

(agent)

INV. NO. 36809