

4-031781

10-26

9 R

15-065-00800-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1959

SW SW SW /4 SEC. 08, 10 S, 21 W
330 feet from S section line
4950 feet from E section line

Operator license# 5285

Lease Wheeler well # 1

Operator: The Dane G. Hansen Trust

County Graham

Address: P.O. Box 187
Logan, Kansas 67646

Well total depth 3900 feet ^{126.75}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 186 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 26 Month: October Year: 92

Plugging proposal received from: Rich Walgren

Company: D.G. Hansen Phone:

Were: Order 325 sx. 65/35 pozmix - 10% gel. - 500# hulls.
Hole open to perf.
Pulled free rods and tubing.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 10:15A.M., Day: 26, Month: October, Year: 92

Actual plugging report: 8 5/8 set @ 186' w/150 sx. cwc. 5 1/2" set @
3875' w/175 cwc. to surface from 1743' w/500 sx. Squeezed 1935' - 1970'
w/400 sx. P.B.T.D. 3640'. Perf. 3577' - 3581'. Test back side cement
at surface. Squeeze 5 1/2" w/325 sx. cement blend w/500# hulls mixed
in to Max. p.S.I. 600#. Close in P.S.I. 300#. Plug compelte.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 2292 GL

I did [X] / did not [] observe the plugging.

Carl Goodrow

DATE 11-23-92

INV. NO. 36853

(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
11-09-1992
NOV 9 1992
CONSERVATION DIVISION
Wichita, Kansas

INVOICED