

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-27307-00-00
Spot: NENWNW Sec/Twnshp/Rge: 10-29S-14E
330 feet from N Section Line, 990 feet from W Section Line
Lease Name: CRAIG Well #: A-1
County: WILSON Total Vertical Depth: 405 feet

Operator License No.: 33539
Op Name: CHEROKEE WELLS LLC
Address: 4916 CP BOWIE BLVD STE 204
FT WORTH, TX 76107

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	44		8 SX

35.00

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/09/2007 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JEFF MORRIS Company: CHEROKEE WELLS LLC Phone: (620) 378-3650

Proposed Plugging Method: RUN 2 3/8" TUBING TO TD OF 405' - PUMP 60/40 POZ MIX TO FILL WELL FROM TD TO SURFACE.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 11/10/2007 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

11-09-07: A 2.375" cement string was lowered to 405'. 140 sacks of 60/40 poz mix with 2% gel was pumped thru the cement string. 11-10-07: The cement had fallen back, therefore the well was topped off with 75 sacks of cement with 2% gel and 3% CaCl. A total of 215 sacks of cement were used to plug well. The well was cut off below plow depth.

Perfs:

INVOICED
DATE 12/26/07
INV. NO 2008060966

RECEIVED
KCC DISTRICT #3

DEC 5 2007 *AMD*
CHANUTE, KS

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 20 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: THIS WELL WAS BEING DRILLED AS A GAS WELL, BUT DRILLER HIT WATER ZONE AND COULD NOT HAUL WATER OFF FAST ENOUGH.

Plugged through: CSG

District: 03

Signed Alan M. Henning
(TECHNICIAN)

PKT