


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Sheridan County, Sec. 28 Twp. 9S Rge. (E) 26 (W)
Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Thunderbird Drilling, Inc.
Lease Name BREEDEN Well No. 1
Office Address 400 N. Woodlawn, Suite 7, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 2, 1967
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced November 2, 1967
Plugging completed November 2, 1967
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Leo Massey of Hays)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4125 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	0	247'	8-5/8"	10/26/67	-----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 1300 Feet;
Plug and 100 sacks cement thru the Drill
Pipe; Mud to 240 Feet; Plug and 25 sacks
cement thru the Drill Pipe; Mud to 40 Feet;
Plug bridged with Kelley and 10 sacks cement
to Base of Cellar; 2 sacks in Rat Hole.
Job completed @ 5 A.M.

RECEIVED
NOV 6 1967
11-06-1967
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sage Drilling Co.
Address 500 Bitting Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wayne W. Kahmeyer of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer
500 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 1967

Louise K. Whitted
Louise K. Whitted - Notary Public.

My commission expires November 26, 1970.

15-179-20054-00-00

DRILLERS LOG

BREEDEN NO. 1

CASING RECORD: 8-5/8" @ 247'
w/150 sax cement

COMPANY: Thunderbird Drilling, Inc.

CONTRACTOR: Sage Drilling Co., Inc.

COMMENCED: October 26, 1967

COMPLETED: November 2, 1967

DESCRIPTION: NE NE SW
Sec. 28-9S-26W
Sheridan Co., Kans

ELEVATION: 2638KB

TOTAL DEPTH: 4125'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	248	
Shale	248	1075	
Shale & Shells w/Sand Streaks	1075	1810	
Shale & Shells	1810	1894	
Dakota	1894	2048	
Shale	2048	2277	
Anhydrite	2277	2344	
Shale & Lime	2344	2709	
Lime & Shale	2709	3958	
Lime	3958	4015	
Lime & Shale	4015	4125	D&A

RECEIVED
NOV 6 1967
11-06-1967
REGISTRATION DIVISION
Topeka, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Lawrence F. Gray
Lawrence F. Gray

Subscribed and sworn to before me this 3rd day of November, 1967.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.