


15-179-00153-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Sheridan County, Sec. 29 Twp. 9S Rge. 26W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW NW
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Friend Well No. 1
Office Address 780 Fourth National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 10 19 59
Application for plugging filed April 10 19 59
Application for plugging approved April 10 19 59
Plugging commenced April 10 19 59
Plugging completed April 10 19 59
Reason for abandonment of well or producing formation No commercial quantities
of oil found.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius, Hill City, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4053 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	210'	210'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set No. 1 Plug at 550' with 20 sacks
cement; Set No. 2 Plug at 220' with
20 sacks cement; Set No. 3 Plug at
40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1959
CONSERVATION DIVISION
Wichita, Kansas
05-06-1959

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Raymond L. Bacon (employee of owner or owner's operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.
(Signature) By: *Raymond L. Bacon* V-P
780 Fourth National Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of May 19 59

My commission expires July 7, 1962

Mona L. Latier
Mona L. Latier Notary Public.

PLUGGING
FILE SEC. 29 T. 9 R. 26W
BOOK PAGE 34 LINE 38

15-179-00153-00-00

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

Friend No. 1
C NW NW Sec. 29-9S-26W
Sheridan County, Kansas

Total Depth: 4053'

Elevation: 2655' RB

Commenced: 3-31-59 Completed: 4-10-59

Production: D & A

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 210' with 165 sacks cement.

Figures indicate bottom of formations:

		<u>TOPS</u>	
Surface Sand	210'		
Shale & Shells	650'	Anhydrite	2234' (/ 421)
Hard Sand & Shale	1450'	Heebner	3778' (-1123)
Shells & Shale	1810'	Toronto	3798' (-1143)
Dakota Sand	2215'	Lansing	3813' (-1158)
Shale & Shells	2234'	Base Kansas City	4045' (-1390)
Anhydrite	2275'	Rotary Total Depth	4053' (-1398)
Shale & Shells	2500'		
Shale & Lime	3725'		
Lime	4053'		
Total Depth	4053'		

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.


IMPERIAL OIL OF KANSAS, INC.

By: 
Vice-President

Subscribed and sworn to before me this 17th day of April, 1959.

My Commission Expires:

July 7, 1962


Mona L. Latier - Notary Public

PLUGGING			
FILE	SEC	T. 9	R. 26W
BOOK	PAGE	34	LINE 38