

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-179-21,038-00-00

LEASE NAME Dean Richards

WELL NUMBER 1

2,310 Ft. from N Section Line

330 Ft. from E Section Line

SEC. 23 TWP. 9 RGE. 27 (E or W)

COUNTY Sheridan

Date Well Completed 5-31-92

Plugging Commenced 5-31-92

Plugging Completed 6-1-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Staab Energy & Leasing

ADDRESS 2514 Haney Drive, Hays, KS. 67601

PHONE#(913) 628-1326 OPERATORS LICENSE NO. 03655

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-31-92 (date)

by Marvin Miller (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4,074'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	217'	Cmtd. w/160 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spot 25 sax cement @2,300' thru drill pipe. Push bridge plug to 1,435', spot 100 sax cement on plug thru drill pipe. Push bridge plug to 265', spot 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 160

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Staab Energy & Leasing

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman (Employee of Contractor or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec. - Treas.

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 16th day of June 1992

Ruth Phillips
Notary Public

My Commission Expires: _____



RECEIVED
STATE CORPORATION, 1992
JUN 17 1992
06-17-1992
CONSERVATION DIVISION
Wichita, Kansas
Forms CP-4
Revised 05-88




Shields

WELL LOG

15-179-21038-00-00 *Russell, Kansas*

Operator: Staab Energy & Leasing
 Well: Dean Richards #1
 Commenced: May 22, 1992
 Completed: May 31, 1992
 Contractor: Shields Drilling Co.

Well Description: SE SE NE
 Sec. 23-9S-27W
 Sheridan Co., Kansas



Elevation: 2,686' KB

Treatment:

Production: D & A

Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	217'	Cmtd. w/160 sax

..... Figures Indicate Bottom of Formations

Sand	220'	
Shale & sand	2,255'	
- Shale	2,287'	
Anhydrite	2,320'	
Shale	2,447'	
Shale & lime	3,846'	
Lime	4,074'	RTD

Notes

RECEIVED
STATE CORPORATION COMMISSION

JUN 17 1992
06-17-1992
CONSERVATION DIVISION
Wichita, Kansas